

URBAN

CODE NO.	ITEM	UNIT	STP FUNDING 80% FEDERAL 20% STATE		CONSTRUCTION TYPE CODE	
			TOTAL QUANTITY	ROADWAY	0005	0011
					SN 045 -0078	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	154	154		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	70	70		
20200100	EARTH EXCAVATION	CU YD	1844	1844		
20300100	CHANNEL EXCAVATION	CU YD	1159		1159	
20400800	FURNISHED EXCAVATION	CU YD	1251	1251		
20800150	TRENCH BACKFILL	CU YD	24	24		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	6675	6675		
21101625	TOPSOIL FURNISH AND PLACE, 6"	SO YD	4877	4877		
25000210	SEEDING, CLASS 2A	ACRE	1.0	1.0		
25000310	SEEDING, CLASS 4	ACRE	0.5	0.5		
25000350	SEEDING, CLASS 7	ACRE	1.5	1.5		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90		
25100630	EROSION CONTROL BLANKET	SO YD	3573	3573		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	400	400		
* 28000305	TEMPORARY DITCH CHECKS	FOOT	90	90		
28000400	PERIMETER EROSION BARRIER	FOOT	3232	3232		
28000500	INLET AND PIPE PROTECTION	EACH	8	8		
28100107	STONE RIPRAP, CLASS A4	SO YD	490		490	
28200200	FILTER FABRIC	SO YD	490		490	
* 30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	6675	6675		
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	517	517		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	49	49		
35501307	HOT-MIX ASPHALT BASE COURSE, 5 3/4"	SO YD	638	638		
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	36	36		
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SO YD	2857	2857		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	255	255		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2411	2411		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	45	45		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	160	160		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	16	16		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	741	741		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	930	930		

URBAN

CODE NO.	ITEM	UNIT	STP FUNDING 80% FEDERAL 20% STATE		CONSTRUCTION TYPE CODE	
			TOTAL QUANTITY	ROADWAY	0005	0011
					SN 045 -0078	
44000100	PAVEMENT REMOVAL	SO YD	5067	5067		
44004250	PAVED SHOULDER REMOVAL	SO YD	398	398		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	454	454		
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	2446	2446		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
50105220	PIPE CULVERT REMOVAL	FOOT	138	138		
50200100	STRUCTURE EXCAVATION	CU YD	49		49	
50300100	FLOOR DRAINS	EACH	8		8	
50300225	CONCRETE STRUCTURES	CU YD	66.3		66.3	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	250.8		250.8	
50300260	BRIDGE DECK GROOVING	SO YD	545		545	
50300300	PROTECTIVE COAT	SO YD	665		665	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500505	STUD SHEAR CONNECTORS	EACH	2394		2394	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	65180		65180	
50800515	BAR SPLICERS	EACH	595		595	
51200957	FURNISHING METAL SHELL PILES 12" X 0.250"	FOOT	530		530	
51202305	DRIVING PILES	FOOT	530		530	
51203200	TEST PILE METAL SHELLS	EACH	2		2	
51500100	NAME PLATES	EACH	1		1	
52100520	ANCHOR BOLTS, 1"	EACH	24		24	
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	100	100		
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	90	90		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	6	6		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2		
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	78		78	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	7	7		
60107600	PIPE UNDERDRAINS 4"	FOOT	214	214		
△ 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	550	550		
△ 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
* △ 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	599	599		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	3.5	3.5	
67100100	MOBILIZATION	L SUM	1	0.5	0.5	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	90	90		

\* SEE SPECIAL PROVISIONS    △ SPECIALTY ITEM

FILE NAME: 4 DISBND-INT-500.dwg  
MODEL: DRIVER 1 VBI.PDF-11-17.dwg  
PLOT: DRIVER 1 VBI.PDF-11-17.dwg



USER NAME: mmpm	DESIGNED: MCV	REVISED:
PLOT SCALE: 1/8"=1'-0"	DRAWN: CMM	REVISED:
PLOT DATE: 10/24/2012	CHECKED: MTM	REVISED:
	DATE: 10/12	REVISED:

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S.    SHEET NO. 1 OF 2 SHEETS    STA.    TO STA.

F.A.P. RTE. 326	SECTION 106X-B	COUNTY KANE	TOTAL SHEETS 87	SHEET NO. 3
CONTRACT NO. 60N13				
ILLINOIS FED. AID PROJECT				