

80% FED. / 20% STATE

80% FED. | 80% FED.
15% STATE | 10% STATE
5% VILLAGE | 10% VILLAGE

SUMMARY OF QUANTITIES

CONSTRUCTION CODE

100% VILLAGE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	RET. WALL	LIGHTING	TS-ZEMKE	TS-HIGGINS	TS-PATTON	WATERMAIN
				0003 URBAN	0040 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0003 URBAN
• 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1			1				
• 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1			1				
• 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1			1				
• 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	1					1	
• 86000100	MASTER CONTROLLER	EACH	1	1						
• 86400100	TRANSCEIVER - FIBER OPTIC	EACH	2				1	1		
• 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	4,213	4,213						
• 87301215	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 2C	FOOT	2079				234	1,845		
• 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	3344				248	3,096		
• 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	9823				4095	3,979	1749	
• 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3093				1201	1,199	693	
• 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	14544				5,319	7,331	1894	
* 87301800	ELECTRIC CABLE IN CONDUIT, SERVICE NO. 4 2C	FOOT	279						279	
• 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	301				190	111		
• 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	4221				1,562	1,816	843	

15 * SPECIALITY ITEM

S00-17

HNTB	USER NAME: lsupencheck	DESIGNED	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE: 1/4" = 1'	DRAWN: MMK	REVISED -					330	0105-WRS	COOK	537	22
	PLOT DATE: 01-NOV-2012	CHECKED: LLS	REVISED -					CONTRACT NO. 60P35				
		DATE: 10/19/12	REVISED -					ILLINOIS FED. AID PROJECT				

FILE NAME: I:\P\p\idms47847\0160P35-ehv-S0017.dgn