

EARTHWORK SCHEDULE - ZEMKE BLVD / BESSIE COLEMAN

BEGIN STATION	END STATION	EARTH EXCAVATION (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE* (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	AGGREGATE SUBGRADE IMPROVEMENT (CU YD)	TOPSOIL (CU YD)	TOPSOIL EXCAVATION AND PLACEMENT (CU YD)
50+75.00	51+00.00	60	0	51	1	50	0	0	0
51+00.00	51+25.00	117	0	99	1	98	0	0	0
51+25.00	51+50.00	114	0	97	1	96	0	0	0
51+50.00	51+75.00	114	0	97	1	96	0	0	0
51+75.00	51+84.52	44	0	37	0	37	0	0	0
51+84.52	52+00.00	72	0	61	1	60	0	0	0
52+00.00	52+25.00	122	0	104	1	103	0	0	0
61+25.00	61+25.00	0	0	0	0	0	0	0	0
61+25.00	61+50.00	103	0	88	0	88	0	0	0
61+50.00	61+75.00	201	0	171	0	171	0	0	0
61+75.00	62+00.00	191	0	162	0	162	0	0	0
62+00.00	62+25.00	180	0	153	0	153	0	0	0
62+25.00	62+50.00	171	0	145	0	145	0	0	0
62+50.00	63+00.00	327	0	278	0	278	0	0	0
63+00.00	63+25.00	154	0	131	0	131	0	0	0
63+25.00	63+50.00	144	0	122	0	122	0	0	0
63+50.00	63+75.00	135	0	115	0	115	0	0	0
63+75.00	64+00.00	126	0	107	1	106	0	0	0
SUB-TOTAL		2,375	0	2,019	7	2,012	0	0	0
9+25.00	9+50.00	106	0	90	0	90	0	0	0
9+50.00	9+75.00	217	0	184	0	184	0	0	0
9+75.00	10+00.00	221	0	188	0	188	0	0	0
10+00.00	10+25.00	214	0	182	0	182	0	0	0
10+25.00	10+50.00	200	0	170	0	170	0	0	0
10+50.00	10+75.00	193	0	164	1	163	0	0	0
10+75.00	11+00.00	192	0	163	2	161	0	0	0
11+00.00	11+25.00	186	0	158	2	156	0	0	0
11+25.00	11+50.00	179	0	152	2	150	0	0	0
11+50.00	11+75.00	180	0	153	1	152	0	0	0
11+75.00	12+00.00	186	0	158	1	157	0	0	0
12+00.00	12+25.00	186	0	158	1	157	0	0	0
12+25.00	12+50.00	184	0	156	1	155	0	0	0
12+50.00	12+75.00	179	0	152	1	151	0	0	0
12+75.00	13+00.00	175	0	149	1	148	0	0	0
13+00.00	13+17.91	124	0	105	0	105	0	0	0
SUB-TOTAL		2,922	0	2,484	13	2,471	0	0	0

* SHRINKAGE FACTOR 25%

SC-05



USER NAME = mkosir	DESIGNED	REVISED -
	DRAWN <i>MMK</i>	REVISED -
PLOT SCALE = 1:1	CHECKED <i>LLS</i>	REVISED -
PLOT DATE = 24-OCT-2012	DATE <i>10/19/12</i>	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	0105-WRS	COOK	537	48
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60P35	