



SCHEDULE OF QUANTITIES

NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL
1	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	809
2	HANDHOLE	EACH	2
3	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
4	MASTER CONTROLLER (SPECIAL)	EACH	1
5	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 141C	FOOT	4,213
6	DRILL EXISTING HANDHOLE	EACH	1
7	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2,442
8	REMOVE EXISTING HANDHOLE	EACH	4
9	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	4,213
10	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1

NOTE:
THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

TS-27



USER NAME = rmemucod	DESIGNED JA	REVISED -
	DRAWN RM	REVISED -
PLOT SCALE = *SCALE*	CHECKED HS	REVISED -
PLOT DATE = 11/29/2012	DATE 10/19/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**INTERCONNECT SCHEMATIC PLAN
IL 72 (HIGGINS RD) FROM US RTE 12-45 (MANNHEIM RD)
TO PATTON DR AND DEVON AVE**

F.A.P. RTE. 330	SECTION 0105-WRS	COUNTY COOK	TOTAL SHEETS 537	SHEET NO. 260
				CONTRACT NO. 60P35
ILLINOIS FED. AID PROJECT				

FILE NAME = c:\caddlib\p\memucod2\p\great.lakes\dms47849\0160P35-sht.ts27.dgn