



THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACTOR'S BID PRICE.

- 1 EACH CONTROLLER AND CABINET COMPLETE
- 361 FOOT SPAN WIRE
- 361 FOOT TETHER WIRE
- 1 LSUM ELECTRIC CABLE AERIAL SUSPENDED
- 8 EACH SIGNAL HEAD, LED, 1-FACE 3-SECTION, SPAN WIRE MOUNTED
- 4 EACH SIGNAL HEAD, LED, 1-FACE 5-SECTION, SPAN WIRE MOUNTED
- 4 EACH TEMPORARY WOOD POLE
- 1 EACH SERVICE INSTALLATION

THE NEW PROPOSED TRAFFIC SIGNAL SYSTEM MUST BE INSTALLED AND FULLY OPERATIONAL BEFORE THE EXISTING TEMPORARY TRAFFIC SIGNAL EQUIPMENT CAN BE DISCONNECTED AND REMOVED.

THE CABLE BETWEEN THE SERVICE INSTALLATION, WHICH IS LOCATED ON THE TEMPORARY TRAFFIC SIGNAL WOOD POLE IN THE NORTHEAST CORNER OF THE INTERSECTION, AND THE COMED POLE SHALL BE DISCONNECTED AND REMOVED. THIS WORK SHALL BE INCLUDED IN THE COST OF "REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT".

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

FILE NAME =	USER NAME = \$USER\$	DESIGNED - PKG	REVISED -
#FILE#		DRAWN - MA	REVISED -
	PLOT SCALE = \$SCALE\$	CHECKED - PKG	REVISED -
	PLOT DATE = \$DATE\$	DATE - 11/12/2012	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>TEMPORARY TRAFFIC SIGNAL INSTALLATION REMOVAL PLAN ILL. ROUTE 72 (HIGGINS RD.) AT PATTON DR.</b>			
SCALE: 1"=20'	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE. 330	SECTION 0105-WRS	COUNTY COOK	TOTAL SHEETS 537	SHEET NO. 262
CONTRACT NO. 60P35				
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT				

**ga** GANDHI AND ASSOCIATES, INC.  
ENGINEERS AND PLANNERS  
6035 N. NORTHWEST HIGHWAY  
SUITE 306  
CHICAGO, ILLINOIS 60631 TEL. 17731774-5910