

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS																100% GLENNVIEW
				ROADWAY	BRIDGE N. BRANCH CHICAGO RIVER	BRIDGE OVER I-94 EDENS EXPY	WILLOW RD AT IL ROUTE 43	WILLOW RD AT THREE LAKES DRIVE	WILLOW RD AT SUNSET RIDGE ROAD	WILLOW RD AT WAGNER RD	WILLOW RD AT PED ONLY CROSSING	WILLOW RD AT OLD WILLOW / NORTHFIELD RD	WILLOW RD AT CENTRAL AV / HAPP ROAD	IL ROUTE 43 AT THREE LAKES DRIVE	INTERCONNECT					
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% NORTHFIELD	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 15% STATE 5% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 10% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 10% NFIELD	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 20% STATE	
0003	0010	0014	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0021	0003		
44004250	PAVED SHOULDER REMOVAL	SQ YD	3526	3526																
44201337	CLASS C PATCHES, TYPE I, 9 INCH	SQ YD	3	3																
44201341	CLASS C PATCHES, TYPE II, 9 INCH	SQ YD	141	141																
44201345	CLASS C PATCHES, TYPE III, 9 INCH	SQ YD	212	212																
44201347	CLASS C PATCHES, TYPE IV, 9 INCH	SQ YD	311	311																
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	13	13																
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	57	57																
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	103	103																
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	45	45																
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	151	151																
48203027	HOT-MIX ASPHALT SHOULDERS, 7 1/2"	SQ YD	182	182																
48203046	HOT-MIX ASPHALT SHOULDERS, 12 1/4"	SQ YD	3372	3372																
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1																
50102400	CONCRETE REMOVAL	CU YD	68.3																	68.3
50104000	BRIDGE RAIL REMOVAL	FOOT	464																	464
50104400	CONCRETE HEADWALL REMOVAL	EACH	3	3																
50157300	PROTECTIVE SHIELD	SQ YD	85																	85
50200100	STRUCTURE EXCAVATION	CU YD	904	459																445
50300225	CONCRETE STRUCTURES	CU YD	104.1	1.5																102.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	778.2	190.6																507.1
50300260	BRIDGE DECK GROOVING	SQ YD	707																	707
50300285	FORM LINER TEXTURED SURFACE	SQ FT	4673	3020																1645
50300300	PROTECTIVE COAT	SQ YD	2039	430																1293
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1																	1
50500505	STUD SHEAR CONNECTORS	EACH	4191																	4191
50800205	REINFORCEMENT BARS, EPOXY COATED	POUNDS	162,506	24396																126510
50800515	BAR SPLICERS	EACH	693																	11,600
50901730	BRIDGE FENCE RAILING	FOOT	464																	464
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	1734																	1734
51202305	DRIVING PILES	FOOT	1734																	1734
51203200	TEST PILE METAL SHELLS	EACH	2																	2
51204650	PILE SHOES	EACH	30																	30

- \* DENOTES SPECIALTY ITEM
- S 80% FEDERAL, 20% NORTHFIELD (ITEP)
- + 90% STATE, 10% NORTHFIELD
- & 40% STATE, 60% NORTHFIELD
- # 100% NORTHFIELD
- NP NON-PARTICIPATING ITEM

Rev. 1-4-13

Rev.

FILE NAME: G:\CH1\0158\Road\Sheets\0160135-SHT-5001.dgn	USER NAME: jrbaldwin	DESIGNED: JLV	REVISED:	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.:	SECTION:	COUNTY:	TOTAL SHEETS:	SHEET NO.:
PLOT SCALE: 40.000' / 1" =	CHECKED: RCB	REVISIONS:	305			(1920,01,1518,2022&1922,4BR)	COOK	919	6	
PLOT DATE: 11/1/2012	DATE: 10/31/2012	REVISIONS:	SCALE: N.T.S. SHEET NO. 6 OF 919 SHEETS			CONTRACT NO. 60T35				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT										