CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE N. BRANCH CHICAGO RIVER	BRIDGE OVER I-94 EDENS EXPY	TRAFFIC SIGNALS: WILLOW RD AT IL ROUTE 43	WILLOW RD AT THREE LAKES DRIVE	WILLOW RD AT SUNSET RIDGE ROAD		WILLOW RD AT WAGNER RD		WILLOW RD AT PED ONLY CROSSING		WILLOW RD AT OLD WILLOW / NORTHFIELD RD		WILLOW RD AT CENTRAL AV / HAPP ROAD		IL ROUTE 43 AT THREE LAKES DRIVE		INTERCONNECT	LIGHTING		UTILITIES	100% GLENVIEW
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% NORTHFIELD	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 15% STATE 5% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 10% NFIELD	80% FED 20% NFIELD ITEP	80% FED 10% STATE 10% NFIELD	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% NFIELD ITEP	80% FED 20% STATE	80% FED 20% STATE	50% FED 50% NFIELD ITEP	100% NORTHFIELD	
				0003	0010	0014	0021	0021	0021		0021		0021		0021		0021		0021		0021	0021		0043	0003
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	101	101																					
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	953	953																					
* 78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	2615	2615																					
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	1711	1711																					
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	11,358	11,358																					
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	7244	7244																					
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	1881	1881																					
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	5379	5379																					
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	1024	1024																					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	895	895																					
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6		6																				
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	1898	1898																					
* 78100300	REPLACEMENT REFLECTOR	EACH	584	584																					
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	600	600																					
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8																					
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	18	18																					
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2																					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	22117	22117																					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	716	716																					
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1																			1			
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1																			1			
* 80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	2				1	1																	
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	5						1		1		1		1										
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	14392				1818	725	732		804		664		962		824				7166			697 $	
* 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	436				89	39	52		37		70		57		92								
* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	2055				68	60	75		98		68		65		45					1576			
* 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	3433				866	587	411		430		110		434		595								
* 81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	90																		90				
* 81200240	CONDUIT EMBEDDED IN STRUCTURE, 2 1/2" DIA., PVC	FOOT	275																			275			
* 81300720	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 12" X 8"	EACH	2																		2				
* 81400100	HANDHOLE	EACH	40				4	4	4		4		3		4		4				9	4			
* 81400200	HEAVY-DUTY HANDHOLE	EACH	23				4	3	4		4				4		4								

* DENOTES SPECIALTY ITEM
$ 80% FEDERAL, 20% NORTHFIELD (ITEP)
\+ 90% STATE, 10% NORTHFIELD
& 40% STATE, 60% NORTHFIELD
\# 100% NORTHFIELD
NP NON-PARTICIPATING ITEM

Rev. 1-7-13

Rev.

FILE NAME = G:\CHI2\0158\Road\Sheets\0160T35-SHT-SD001.dgn	USER NAME = mnbaldwin	DESIGNED - JLV	REVISED -
		DRAWN - JRS	REVISED -
	PLOT SCALE = 40.000 ' / in.	CHECKED - RCB	REVISED -
	PLOT DATE = 11/1/2012	DATE - 10/31/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. | SHEET NO. 13 OF 919 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	(1920.01,1518.2022&1922.4B)R	COOK	919	13
		CONTRACT NO. 60T35		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		