

INDEX OF SHEETS

1. TITLE SHEET
2. INDEX OF SHEETS, STATE STANDARDS & GENERAL NOTES
3. SUMMARY OF QUANTITIES
4. LOCATION MAPS
- 5-6. BRIDGE PLANS LOCATION 1 (SN 016-0831)
- 7-8. BRIDGE PLANS LOCATION 2 (SN 016-1136)
- 9-10. BRIDGE PLANS LOCATION 3 (SN 016-0694)
11. PERMANENT PROTECTIVE SHIELDING DETAILS
12. TRAFFIC CONTROL DETAILS FOR FREEWAY SINGLE & MULTI-LANE WEAVE (TC-9)
13. TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURE AND PARTIAL RAMP CLOSURES (TC-17)

STATE STANDARDS

- 701101-03 OFF-RD OPERATIONS, MULTILANE, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
- 701400-06 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701401-07 LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701411-08 LANE CLOSURE, MULTILANE AT ENTRANCE OR EXIT RAMP FOR SPEEDS \geq 45 MPH
- 701446-04 TWO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701901-03 TRAFFIC CONTROL DEVICES

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION) AT (1-800)-892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4151 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM BRIDGE INSPECTORS.

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED AT THE UNIT PRICE BID FOR THE WORK.

THE CONTRACTOR SHALL RELOCATE ANY CONDUIT ATTACHED TO THE FLANGE PRIOR TO THE INSTALLATION OF THE PROTECTIVE SHIELDING. UNDER NO CIRCUMSTANCES SHALL THE PROTECTIVE SHIELDING REST ON TOP OF THE CONDUIT.

ANY WORK DONE BY THE CONTRACTOR ON THE UNDERPASS LIGHTING SYSTEM WILL REQUIRE A TRANSFER OF MAINTENANCE OF THE EFFECTED CIRCUITS TO THE CONTRACTOR. ALTERNATIVELY, THE CONTRACTOR CAN AVOID A MAINTENANCE TRANSFER BY HIRING THE DEPARTMENT'S ELECTRICAL MAINTENANCE CONTRACTOR (EMC) TO RELOCATE THE CONDUIT.

WHERE UNDERPASS LIGHTING IS PRESENT ON A STRUCTURE, THE CONTRACTOR SHALL ADJUST THE PROTECTIVE SHIELDING TO RIDE ABOVE THE EXISTING LIGHTING FIXTURES IN ORDER TO MAINTAIN THE EXISTING LEVEL OF LIGHTING ON THE ROADWAY UNDERNEATH. DETAILS SHALL BE APPROVED BY THE ENGINEER BEFORE INSTALLATION. A CLEARANCE OF 1 1/2 " \pm 1/4 " AROUND THE FIXTURE SHALL BE PROVIDED FOR FUTURE MAINTENANCE.

ANY ADJUSTMENT DONE TO THE PROTECTIVE SHIELD SYSTEM MUST NOT CHANGE THE LOAD CARRYING CAPACITY OR CONTAINMENT SPECIFICATIONS AS INDICATED ON THE PERMANENT PROTECTIVE SHIELDING DETAILS LOCATED IN THE PLANS. COST OF ADJUSTING SHIELDING IS INCLUDED IN THE COST OF PROTECTIVE SHIELD (PERMANENT).

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THE LOCATION OF ALL FIBER OPTIC UTILITIES PRIOR TO STARTING CONSTRUCTION. THE CONTRACTOR SHALL INITIATE THE LOCATE PROCESS FOR THE FIBER OPTIC CABLE BY COMPLETING A "REQUEST TOLLWAY UTILITIES LOCATE" FORM ON THE TOLLWAY WEBSITE UNDER "DOING BUSINESS" AT LEAST FOUR (4) BUSINESS DAYS PRIOR TO STARTING ANY UNDERGROUND OPERATIONS, EXCAVATIONS OR DIGGING OF ANY TYPE IN GENERAL AREA OF THE FIBER OPTIC CABLE.

CONTRACTOR MUST COMPLETE WORK WITHOUT DISTURBING THE EXISTING LIGHTING AND SURVEILLANCE CONDUIT OR JUNCTION BOXES. IF INSTALLATIONS ARE DAMAGED IN THE PROCESS, CONTRACTOR SHALL REPAIR OR REPLACE EXISTING ELECTRICAL INSTALLATIONS IN COMPLIANCE WITH ELECTRICAL OR SURVEILLANCE CONSTRUCTION SPECIFICATIONS.

FILE NAME *	USER NAME * pgrzanowski	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES	F.A.I. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
ct:\pgr\work\pgr\pgrzanowski\0310230	0141012-sht-plan.dgn	DRAWN -	REVISED -			04 & 290	2012-0241	COOK	13	2		
	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -									
	PLOT DATE = 9/28/2012	DATE -	REVISED -									
						SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT
											CONTRACT NO. 60T69	