

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	100-1 STATE TOTAL QUANTITIES	0005				CODE NO	ITEM	UNIT	100-1 STATE TOTAL QUANTITIES	0005				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	19	19				44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	167	167				
25200110	SODDING, SALT TOLERANT	SO YD	19	19				48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	671	671				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	45	45				60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	3	3				
40600300	AGGREGATE (PRIME COAT)	TON	222	222				67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	84	84				67100100	MOBILIZATION	L SUM	1	1				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3875	3875				70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	1538	1538				70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5918	5918				70300100	SHORT TERM PAVEMENT MARKING	FOOT	2391	2391				
42001300	PROTECTIVE COAT	SO YD	22	22				70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	292	292				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	14988	14988				70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	38981	38981				
44022029	PARTIAL DEPTH REMOVAL 3"	SO YD	5998	5998				70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1038	1038				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	416	416				70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1341	1341				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	250	250				70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	70	70				

URBAN

URBAN

5998 5998

Rev. 1-9-13 SPECIALTY ITEMS

FILE NAME	USER NAME	DESIGNED	REVISIONS	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	350	350	350			F.A.P. 350/ IL. 50 (CICERO AVE.)--STEEGER RD. TO GOVERNORS HWY.		350	(101W-EXT-RIRS)	WILL	31	3
SCALE:	SHEET NO.	OF SHEETS	STA.			TO STA.		CONTRACT NO. 60V65				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT												