

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT							
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	15480	15480					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	292	292					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	38981	38981					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1038	1038					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1341	1341					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	70	70					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	909	909					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	818	818					
*85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1					
*87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	880	880					
*87900200	DRILL EXISTING HANDHOLE	EACH	4	4					
*88500100	INDUCTIVE LOOP DETECTOR	EACH	3	3					

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT							
*88600100	DETECTOR LOOP, TYPE I	FOOT	220	220					
*89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	770	770					
*X0324599	ROD AND CLEAN EXISTING CONDUIT	FOOT	700	700					
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	168	168					
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SO YD	22954	22954					
X4421000	PARTIAL DEPTH PATCHING	TON	1008	1008					
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	113	113					
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					

FILE NAME	USER NAME	DESIGNED	REVISED
DRAWN	CHECKED	DATE	

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES
F.A.P. 350/ IL. 50 (CICERO AVE.)--STEEGER RD. TO GOVERNORS HWY.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	101W-EXT-RIRS	WILL	31	4
CONTRACT NO. 60V65				

Rev. 1-9-13

* SPECIALTY ITEMS