SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0005
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	15480	15480
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	292	292
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	38981	38981
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1038	1038
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1341	1341
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	70	70
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	909	909
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	818	818
*85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1
*87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	880	880
*87900200	DRILL EXISTING HANDHOLE	EACH	4	4
*88500100	INDUCTIVE LOOP DETECTOR	EACH	3	3

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0005
*88600100	DETECTOR LOOP, TYPE I	FOOT	220	220
*89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	770	770
*X0324599	ROD AND CLEAN EXISTING CONDUIT	FOOT	700	700
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	168	168
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	22954	22954
X4421000	PARTIAL DEPTH PATCHING	TON	396	396
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	113	113
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\pw_00\sfeedpro\d0515120\D04513_sht_plan.dgn
USER NAME = swedpo
PLOT SCALE = 1000.000 ' / in.
PLOT DATE = 10/30/2002

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
F.A.P. 350/ IL. 50 (CICERO AVE.)--STEGER RD, TO GOVERNORS HWY.

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	(101W-EXT-R)RS	WILL	31	4

CONTRACT NO. 60V65

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT