

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20	20					
40600300	AGGREGATE (PRIME COAT)	TON	99	99					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	39	39					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	982	982					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	433	433					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2176	2176					
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	20	20					
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	2739	2739					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	23369	23369					
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	20	20					
44201777	CLASS D PATCHES, TYPE II, 1/ INCH	SO YD	100	100					
44201781	CLASS D PATCHES, TYPE III, 1/ INCH	SO YD	100	100					
44201783	CLASS D PATCHES, TYPE IV, 1/ INCH	SO YD	200	200					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	5	5					

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	5	5					
60300410	VALVE BOX FRAMES TO BE ADJUSTED WITH NEW FRAMES	EACH	5	5					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	14898	14898					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	711.3	711.3					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4046	4046					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3250	3250					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	235	235					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	792	792					