ITEM NO.	SPECIALTY ITEM	SP	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	RECONSTRUCTION, CAPACITY ADDED	BRIDGE, NEW CONSTRUCTION	SAFETY (TRAFFIC SIGNALS, LIGHTING, SIDEWALKS, EVPS)
							0003	0008	0021
							100% STATE	100% STATE	
1			20100500	TREE REMOVAL, ACRES	ACRE	4.00		4.00	
2			20200100	EARTH EXCAVATION	CU YD	10,465	5,415	5,050	
3			20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	16,930		16,930	
4			20400800	FURNISHED EXCAVATION	CU YD	111,479 △1		111,479 △1	
5			20700220	POROUS GRANULAR EMBANKMENT	CU YD	5,201		5,201	
6			20800150	TRENCH BACKFILL	CU YD	46	46		
7			21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,055		1,055	
8			21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	33,070		33,070	
9			21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	250	250		
10			25000350	SEEDING, CLASS 7	ACRE	14.75	13.50	1.25	
11			25100135	MULCH, METHOD 4	ACRE	12.50	11.25	1.25	
12			25100630	EROSION CONTROL BLANKET	SQ YD	43,115	10,045	33,070	
13			25100900	TURF REINFORCEMENT MAT	SQ YD	26,797		26,797	
14			28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	48,785	14,946	33,839	

14

△1 Rev. 1-3-13

HDR ENGINEERING, INC.

USER NAME = user	DESIGNED - LGP	REVISED -
	DRAWN - ML	REVISED -
PLOT SCALE = $SCALE$	CHECKED - LGP	REVISED -
PLOT DATE = 11/2/2012	DATE - 11-02-2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL ROUTE 19 (IRVING PARK RD.) AND YORK RD.

NTS | SHEET NO. 1 OF 13 SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	32VB	DUPAGE	388	7

CONTRACT NO. 60W01

ILLINOIS FED. AID PROJECT