



NOTES:

1. FOR SIGNS, USE BLACK LETTERING ON ORANGE BACKGROUND.
2. SIGNS SHALL BE INSTALLED WITHIN TOLLWAY OR IDOT RIGHT-OF-WAY, WITH A MINIMUM SPACING OF 400 FEET FROM OTHER GUIDE SIGNS, AND 200 FEET FROM ALL OTHER SIGNS.
3. CONTRACTOR SHALL INSTALL SIGNING WITH TRUCK DETOUR SIGNING BEFORE PROPOSED CPR BRIDGE BEAMS ARE ERRECTED IN STAGE 2, OR AS DIRECTED BY THE ENGINEER.
4. SEE SPECIAL PROVISIONS FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
5. ONE SIGN INTERSTATE SIGN ASSEMBLY EQUALS 40.0 SQ. FT. ONE SIGN ARTERIAL SIGN ASSEMBLY EQUALS 72.0 SQ. FT.
6. SIGNS, POSTS, AND MOUNTING BRACKETS SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.
7. LOCATIONS ARE APPROXIMATE. EXACT LOCATIONS TO BE FIELD VERIFIED AND APPROVED BY THE ENGINEER.

ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SHOWN.



USER NAME * user	DESIGNED - JJS	REVISED - 12/28/2012 MPK
	DRAWN - TT	REVISED -
PLOT SCALE * #SCALE#	CHECKED - LGP	REVISED -
PLOT DATE * 12/28/2012	DATE - 08-03-2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

MOT DETAIL- ADVANCE WARNING SIGNS

SCALE: NTS SHEET NO. 25 OF 29 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	32 WRS-5	DUPAGE	388	74
CONTRACT NO. 60842			ILLINOIS FED. AID PROJECT	