

ITEM NO.	SPECIALTY ITEM	SP	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	RECONSTRUCTION, CAPACITY ADDED	BRIDGE, NEW CONSTRUCTION	SAFETY (TRAFFIC SIGNALS, LIGHTING, SIDEWALKS, EVPS)
							0003	0008	0021
							100% STATE	100% STATE	
29			50105220	PIPE CULVERT REMOVAL	FOOT	98	58	40	
30			50200100	STRUCTURE EXCAVATION	CU YD	1,296		1,296	
31			50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	7,094		7,094	
32			50300285	FORM LINER TEXTURED SURFACE	SQ FT	24,244		24,244	
33			50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
34			50800105	REINFORCEMENT BARS	POUND	70,310		70,310	
35			50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	895,580		895,580	
36			50901750	PARAPET RAILING	FOOT	872		872	
37			51201900	FURNISHING STEEL PILES HP14X89	FOOT	32,366		32,366	
38			51202305	DRIVING PILES	FOOT	32,366		32,366	
39			51203900	TEST PILE STEEL HP14X89	EACH	9		9	
40			51204650	PILE SHOES	EACH	110		110	
41			51500100	NAME PLATES	EACH	8		8	
42			52100540	ANCHOR BOLTS, 1 1/2"	EACH	60		60	



USER NAME - user	DESIGNED - MPK	REVISED -
PLOT SCALE - #SCALE#	DRAWN - ML	REVISED -
PLOT DATE - 11/2/2012	CHECKED - LGP	REVISED -
	DATE - 11-02-2012	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
IL ROUTE 19 (IRVING PARK RD.) AND YORK RD.

SCALE: NTS SHEET NO. 3 OF 13 SHEETS STA. TO STA.

F.A.U. RTE. 1321	SECTION 32V8	COUNTY	TOTAL SHEETS 388	SHEET NO. 9
CONTRACT NO. 60W01			ILLINOIS FED. AID PROJECT	

Rev.