



TEMPORARY ADVANCE EVP POST DETAIL

NOTES:

- CONTRACTOR SHALL INSTALL ADDITIONAL 30' CLASS 5 OR BETTER WOOD POLES AS NECESSARY FOR ROUTING OF AERIAL CABLE TO EVP UNIT MOUNTED ON 3' BY 3' BY 3' CONCRETE BLOCK WITH LIFTING EYES WITH 18' POST. CONTRACTOR SHALL ROUTE UNDERGROUND CONDUIT AS NECESSARY TO PASS UNDER UPRR BRIDGE. CONDUIT SHALL BE AT SUFFICIENT DEPTH TO PROTECT CONDUIT FROM REMOVAL OF TEMPORARY PAVEMENT AND ALL OTHER CONSTRUCTION ACTIVITIES FOR DURATION OF CONTRACT. PLACEMENT OF TEMPORARY POST FOR EVP SHALL BE AT APPROXIMATELY STATION 403+50 AND CONTRACTOR SHALL ADJUST LOCATION AS NECESSARY TO OBTAIN OPTIMAL POSITION TO THE SATISFACTION OF THE ENGINEER. CONTRACTOR SHALL FURNISH AND INSTALL SOLAR FLASHING BEACON ON TEMPORARY POST AS SHOWN IN DETAIL THIS SHEET AND SHEET 97. POLE LOCATIONS AS SHOWN ARE ONLY APPROXIMATE AND SHALL BE DETERMINED IN THE FIELD.

USER NAME = Singh Office	DESIGNED - VP	REVISED -
PLOT SCALE = #SCALE#	DRAWN - YJ	REVISED -
PLOT DATE = 11/15/2012	CHECKED - LGP/GR	REVISED -
	DATE - 11-02-2012	REVISED -

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	32VB	DUPAGE	371	115
CONTRACT NO. 60W01				
ILLINOIS FED. AID PROJECT				