

SCHEDULE OF QUANTITIES

1 SCHEDULE OF SUB GRADES, SUBBASES AND BASE COURSE					
FROM	TO	AGGREGATE SUBGRADE IMPROVEMENT 12" (30300112) (SQ YD)	AGGREGATE BASE COURSE TYPE B (35101500) (CU YD)	AGGREGATE BASE COURSE TYPE B 6" (35101800) (SQ YD)	CEMENT CONCRETE BASE COURSE 10" (35300500) (SQ YD)
547+04	551+00	678	4	0	331
551+00	556+00	1,611	19	0	1,066
556+50	562+00	872	21	0	317
562+00	564+66	350	3	0	127
574+12	577+00	294	5	0	92
577+00	582+50	1,211	102	0	523
582+50	588+00	1,111	24	0	687
588+00	591+09	428	6	0	185
U.S. 14 SUBTOTAL		6,556	184	0	3,328
13+52	18+75	3,050	18	0	0
18+75	22+17	2,482	17	160	0
DAVIS STREET SUBTOTAL		5,502	35	160	0
904+75	908+00	2,408	45	0	0
908+00	910+00	447	3	0	0
ARTHUR AVENUE SUBTOTAL		2,855	48	0	0
PROJECT TOTAL		14,913	267	160	3,328

2 SCHEDULE OF POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE MIX "F" N90 (40603595)				
FROM	TO	AREA @ 2.25" (SQ FT)	AREA @ 2.25" (SQ YD)	TON
547+04	551+00	23515	2,813	256
551+00	556+50	39941	4,438	435
556+50	562+00	36055	4,006	393
562+00	564+66	16819	1,869	183
574+12	577+00	17492	1,944	190
577+00	582+50	40859	4,540	445
582+50	588+00	33316	3,702	363
588+00	591+09	17891	1,988	195
U.S. 14 SUBTOTAL			25,099	2,460
13+52	18+75	0	0	0
18+75	22+17	0	0	0
DAVIS STREET			0	0
904+75	908+00	0	0	0
908+00	910+00	0	0	0
ARTHUR AVENUE			0	0
PROJECT TOTAL				2,460

3 SCHEDULE OF HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH) 8-1/4" (40701846)			
STATION		SQ FT	SQ YD
FROM	TO		
547+04	551+00	0	0
551+00	556+50	0	0
556+50	562+00	0	0
562+00	564+66	0	0
574+12	577+00	0	0
577+00	582+50	0	0
582+50	588+00	0	0
588+00	591+09	0	0
U.S. 14 SUBTOTAL			0
13+52	18+75	23410	2,601
18+75	22+17	22368	2,485
DAVIS STREET SUBTOTAL			5,086
904+75	908+00	12591	1,399
908+00	910+00	9244	1,027
ARTHUR AVENUE SUBTOTAL		21835	2,426
PROJECT TOTAL		21,835	7,513

INDEX TO SCHEDULES OF QUANTITIES		
NO.	DESCRIPTION	SHEET NO.
1	SCHEDULE OF SUB GRADES, SUBBASES AND BASE COURSE	11
2	SCHEDULE OF POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE MIX "F" N90	11
3	SCHEDULE OF HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH) 8-1/4"	11
4	SCHEDULE OF EARTH EXCAVATION AND FURNISHED EXCAVATION	12 to 14
5	SCHEDULE OF HOT-MIX ASPHALT DRIVEWAY PAVEMENT	15
6	SCHEDULE OF PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT	15
7	SCHEDULE OF PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	15
8	SCHEDULE OF REMOVAL ITEMS	15
9	SCHEDULE OF STORM SEWERS AND TRENCH BACKFILL	15
10	SCHEDULE OF STORM SEWER STRUCTURES	16
11	SCHEDULE OF STORM SEWER REMOVAL	16
12	SCHEDULE OF CURBS AND MEDIANS	16

DATE	
BY	
REVISION	
NO.	
DATE	
BY	
REVISION	
NO.	

DATE	
BY	
REVISION	
NO.	
DATE	
BY	
REVISION	
NO.	



USER NAME = #USER#	DESIGNED - RTM	REVISED -
PLDT SCALE = #SCALE#	DRAWN - JRR	REVISED -
PLDT DATE = #DATE#	CHECKED - RTM	REVISED -
	DATE - 10/22/12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SHEET NO 1 OF 6 SHEETS

F.A.U. RIE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3512	02-00177-00 WR	COOK	142	11
PROJECT NO. M-8003(426)			CONTRACT NO. 63514	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				