

# SCHEDULE OF QUANTITIES

4 SCHEDULE OF EARTH EXCAVATION AND FURNISHED EXCAVATION													
U.S. Route 14 / Davis Street / Arthur Avenue													
STATION	DISTANCE	EARTH EXCAVATION (CUT)	UNSUITABLE AREA	AGGREGATE SUBGRADE IMPROVEMENT	FURNISHED EXCAVATION (FILL)	EARTH EXCAVATION	UNSUITABLE AREA	AGGREGATE SUBGRADE IMPROVEMENT	FURNISHED EXCAVATION	EARTH EXCAVATION (CUT)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	AGGREGATE SUBGRADE IMPROVEMENT	FURNISHED EXCAVATION (FILL)
PROJECT OMISSION		PROJECT OMISSION STATION 564+66 TO STATION 574+12				PROJECT OMISSION STATION 564+66 TO STATION 574+12				PROJECT OMISSION STATION 564+66 TO STATION 574+12			
574+00		0	0	0	0								
574+50	50	19	8	8	3	10	4	4	2	475	200	200	75
575+00	50	14	7	7	3	17	8	8	3	825	375	375	150
575+50	50	18	10	10	2	16	9	9	3	800	425	425	125
576+00	50	17	8	8	6	18	9	9	4	875	450	450	200
576+50	50	19	10	10	7	18	9	9	7	900	450	450	325
577+00	50	23	11	11	3	21	11	11	5	1,050	525	525	250
577+50	50	7	5	5	1	15	8	8	2	750	400	400	100
578+00	50	17	11	11	3	12	8	8	2	600	400	400	100
578+50	50	29	11	11	5	23	11	11	4	1,150	550	550	200
579+00	50	57	0	0	3	43	6	6	4	2,150	275	275	200
579+50	50	28	0	0	3	43	0	0	3	2,125	0	0	150
580+00	50	38	0	0	2	33	0	0	3	1,650	0	0	125
580+50	50	37	0	0	2	38	0	0	2	1,875	0	0	100
581+00	50	44	0	0	2	41	0	0	2	2,025	0	0	100
581+50	50	56	0	0	2	50	0	0	2	2,500	0	0	100
582+00	50	50	0	0	2	53	0	0	2	2,650	0	0	100
582+50	50	37	0	0	3	44	0	0	3	2,175	0	0	125
583+00	50	40	0	0	2	39	0	0	3	1,925	0	0	125
583+50	50	40	0	0	2	40	0	0	2	2,000	0	0	100
584+00	50	28	0	0	6	33	0	0	4	1,650	0	0	200
584+50	50	35	0	0	4	31	0	0	5	1,525	0	0	250
585+00	50	26	0	1	7	31	0	1	6	1,525	0	25	275
585+50	50	33	0	1	4	30	0	1	6	1,475	0	50	275
586+00	50	36	0	0	3	35	0	1	4	1,725	0	25	175
586+50	50	38	0	0	2	37	0	0	3	1,850	0	0	125
587+00	50	31	0	0	6	35	0	0	4	1,725	0	0	175
587+50	50	27	6	6	3	29	3	3	4	1,450	150	150	200
588+00	50	35	8	8	2	31	7	7	3	1,550	350	350	125
588+50	50	37	7	7	3	36	8	8	3	1,800	375	375	125
589+00	50	29	6	6	3	33	7	7	3	1,650	325	325	150
589+50	50	16	5	5	2	23	6	6	3	1,125	275	275	125
590+00	50	18	5	5	3	17	5	5	3	850	250	250	125
590+50	50	13	3	3	3	16	4	4	3	775	200	200	150
591+00	25	14	3	3	2	14	3	3	3	675	150	150	125
591+25		0	0	0	0	7	2	2	1	175	38	38	25
SUBTOTAL U.S. ROUTE 14										95,175	14,513	14,663	11,798

PLAN	DATE
BY	DATE
SURVEYED	DATE
PLOTTED	DATE
NOTE BOOK	DATE
NO.	DATE

PROFILE	DATE
BY	DATE
SURVEYED	DATE
PLOTTED	DATE
NOTE BOOK	DATE
NO.	DATE



USER NAME = #USER#	DESIGNED - RTM	REVISED -
PLOT SCALE = #SCALE#	DRAWN - JRR	REVISED -
PLOT DATE = #DATE#	CHECKED - RTM	REVISED -
	DATE - 10/22/12	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SHEET NO 3 OF 6 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3512	Q2-00177-00 WR	COOK	142	J3
PROJECT NO. M-8003(426)		CONTRACT NO. 63514		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				