



**NOTES:**

- REFER TO DRAWING E1 FOR GENERAL NOTES, LEGEND AND ABBREVIATIONS.
- REFER TO DRAWINGS E15 THRU E20 FOR DETAILS.
- REFER TO DRAWING E21 FOR LIGHT POLE SCHEDULE AND DRAWING E22 FOR LIGHTING SINGLE LINE DIAGRAM.
- ELECTRICAL CONTRACTOR SHALL DISCONNECT EXISTING LIGHT POLE POWER FEEDS FROM SUPPLY POINTS. EXISTING UNDERGROUND WIRING/CONDUITS SHALL BE ABANDONED IN PLACE. EXISTING POLES/FIXTURES BEING REMOVED SHALL BE TURNED OVER TO THE VILLAGE OF ARLINGTON HEIGHTS. EXISTING FOUNDATION SHALL BE REMOVED COMPLETELY.
- LOCATION OF EXISTING LIGHT POLES IS APPROXIMATE. FIELD VERIFY EXACT LOCATION.
- THE CONTRACTOR SHALL REMOVE TEMPORARY LIGHT POLE AND ASSOCIATED TEMPORARY CIRCUIT, CABLE, FOUNDATION, FIXTURE, ETC. AFTER NEW LIGHT POLES AND LIGHT FIXTURES ARE ACCEPTED BY VILLAGE OF ARLINGTON HEIGHTS. PROVIDE BACKFILL FOR ALL TEMPORARY FOUNDATIONS, MATCH WITH EXISTING GROUND.
- LOCATION OF EXISTING CONDUIT AND CABLE IS APPROXIMATE. FIELD VERIFICATION REQUIRED FOR EXACT LOCATION OF CONDUIT ROUTING.

BEGIN IMPROVEMENT  
STA. 13+52



REVISIONS	
NAME	DATE

VILLAGE OF ARLINGTON HEIGHTS  
**DEMOLITION PLAN-2**  
U.S. ROUTE 14  
STA. 551+00 TO STA. 557+00

DATE: 08/17/2012  
DESIGNED BY: EE  
TECHNICIAN: EE  
CHECKED BY: DEM

E8 OF E24

