

REMOVAL SCHEDULE									
SHEET	LOCATION	PAVEMENT REMOVAL	DRIVEWAY PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	PAVED SHOULDER REMOVAL	MANHOLES TO BE ADJUSTED	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS
	STATION TO STATION	44000100 SQ YD	44000200 SQ YD	44000500 FOOT	44004250 SQ YD	60255500 EACH	60500040 EACH	60500050 EACH	60500060 EACH
REMOVAL PLAN - SHEET 1 OF 2	STA. 101+57.24 TO STA. 106+00.00	1313.2	160.4	845.6	0.0	1	1	2	0
REMOVAL PLAN - SHEET 1 OF 2	STA. 106+00.00 TO STA. 112+20.00	2539.4	356.3	650.7	0.0	1	2	6	1
REMOVAL PLAN - SHEET 2 OF 2	STA. 65+66.79 TO STA. 70+25.00	657.4	0.0	0.0	408.0	1	0	0	0
REMOVAL PLAN - SHEET 2 OF 2	STA. 72+00.00 TO STA. 77+34.82	1399.8	164.9	0.0	0.0	1	0	0	0
TOTAL		5910	682	1497	408	4	3	8	1

PAVEMENT MARKING SCHEDULE							
SHEET	LOCATION	THERMOPLASTIC PLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	THERMOPLASTIC PLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PLASTIC PAVEMENT MARKING - LINE 5"	THERMOPLASTIC PLASTIC PAVEMENT MARKING - LINE 8"	THERMOPLASTIC PLASTIC PAVEMENT MARKING - LINE 12"	RAISED REFLECTIVE PAVEMENT MARKER
	STATION TO STATION	78000100 SQ FT	78000200 FOOT	78000300 FOOT	78000500 SQ YD	78000600 EACH	78100100 EACH
PAVEMENT MARKING PLAN - SHEET 1 OF 2	STA. 101+57.24 TO STA. 107+75.00	149	1660	1239	576	474	26
PAVEMENT MARKING PLAN - SHEET 1 OF 2	STA. 107+75.00 TO STA. 112+20.00	0	1487	786	51	58	2
PAVEMENT MARKING PLAN - SHEET 2 OF 2	STA. 67+95.35 TO STA. 70+00.00	0	663	304	27	26	2
PAVEMENT MARKING PLAN - SHEET 2 OF 2	STA. 72+25.00 TO STA. 77+34.82	0	1630	914	37	58	2
TOTAL		149	5440	3243	691	616	32

FILE NAME = L:\AKCED\1122481\Drawings\1000_Sheets\Schedule of Quantities.dwg



USER NAME = Jeff Sedig	DESIGNED - MNB	REVISED -
PLOT SCALE = 48.0000' / 1"	DRAWN - MNB	REVISED -
PLOT DATE = 11/12/2012	CHECKED - CMC	REVISED -
	DATE - 10/22/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE:		SHEET NO. 2 OF 3 SHEETS		STA. -	TO STA. -
--------	--	-------------------------	--	--------	-----------

F.A.U. RTE. 0192	SECTION 06-00153-07-CH	COUNTY LAKE	TOTAL SHEETS 120	SHEET NO. 7
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 63682				