

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	004 RECONSTRUCTION	021 TRAFFIC SIGNALS	021 LIGHTING	042 TRAINEES
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
Z0018804	TEMPORARY DRAINAGE SYSTEM NO. 1	FOOT	340	340			
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52			
* Z0033044	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	1		1		
Z0062456	TEMPORARY PAVEMENT	SQ YD	2,500	2,500			
* Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1	1			
Z0076600	TRAINEES	HOUR	1,000				1,000
Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	1,000				1,000
XX008749	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 23 FRAME AND GRATE, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	3	3			
XX008750	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 23 FRAME AND GRATE, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1			
XX006055	MANHOLES, TYPE A, 7'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	2	2			
* 88060410	COMBINATION SIGNAL HEAD, LED, 3-FACE, 2-3 SECTION OPTICALLY PROGRAMMED, 1-3 SECTION, BRACKET MOUNTED	EACH	2	2			
* 88060415	COMBINATION SIGNAL HEAD, LED, 3-FACE, 2-3 SECTION OPTICALLY PROGRAMMED, 1-5 SECTION, BRACKET MOUNTED	EACH	1	1			
A 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	125	125			
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1			
66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1			

* SPECIALTY ITEM

FILE NAME = 4185.800-DT1.dwg

USER NAME = PAUL SWIA TEK

DESIGNED - BVS

REVISED - A 12/18/12

PLOT SCALE = 1" = .0833'

DRAWN - PJS

REVISED -

PLOT DATE = 10/17/2012

CHECKED - KLB

REVISED -

DATE - 10/17/12

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
KENSINGTON ROAD IMPROVEMENTS**

SCALE N.T.S. SHEET NO. OF SHEETS STA. TO STA.

FAU RTE

1295

SECTION

09-00154-00-PV

COUNTY

COOK

TOTAL SHEETS

119

SHEET NO.

11

CONTRACT # 63746

ILLINOIS FED. AID PROJECT