

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	004 RECONSTRUCTION	021 TRAFFIC SIGNALS	021 LIGHTING	042 TRAINEES
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N50	TON	235	235			
40701891	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 10 1/2"	SQ YD	13,220	13,220			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	10	10			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	790	790			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	16,145	16,145			
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	1,480	1,480			
42400800	DETECTABLE WARNINGS	SQ FT	472	472			
44000100	PAVEMENT REMOVAL	SQ YD	9,950	9,950			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	2,675	2,675			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,435	2,435			
44000300	CURB REMOVAL	FOOT	170	170			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4,680	4,680			
44000600	SIDEWALK REMOVAL	SQ FT	9,975	9,975			
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	30	30			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2,070	2,070			
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTION 12"	EACH	1	1			
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	2,470	2,470			
550A2530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 15"	FOOT	205	205			
550A2560	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 24"	FOOT	865	865			
550A2580	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 30"	FOOT	55	55			
550A2600	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 36"	FOOT	665	665			
550A2620	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 48"	FOOT	735	735			
550A2640	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 60"	FOOT	285	285			
55100300	STORM SEWER REMOVAL 8"	FOOT	250	250			
55100400	STORM SEWER REMOVAL 10"	FOOT	125	125			
55100500	STORM SEWER REMOVAL 12"	FOOT	490	490			
55100700	STORM SEWER REMOVAL 15"	FOOT	1,705	1,705			
55100900	STORM SEWER REMOVAL 18"	FOOT	30	30			

* SPECIALTY ITEM

FILE NAME = 4185.800-DTI.dwg

USER NAME = PAUL SWIATEK

DESIGNED - BVS

REVISED -

PLOT SCALE = 1" = 60.33'

DRAWN - PJS

REVISED -

PLOT DATE = 10/17/2012

CHECKED - KLB

REVISED -

DATE - 10/17/12

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
KENSINGTON ROAD IMPROVEMENTS**

SCALE N.T.S. SHEET NO. OF SHEETS STA. TO STA.

FAU
RTE

1295

SECTION

09-00154-00-PV

COUNTY

COOK

TOTAL SHEETS

119

SHEET NO.

06

CONTRACT # 63746

ILLINOIS FED. AID PROJECT