

**SUMMARY OF QUANTITIES**

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	004 RECONSTRUCTION	021 TRAFFIC SIGNALS	021 LIGHTING	042 TRAINEES
60201330	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	15	15			
60203905	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60205030	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	1	1			
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	3	3			
60208230	CATCH BASINS, TYPE C, TYPE 23 FRAME AND GRATE	EACH	33	33			
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	14	14			
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1			
60219530	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	1	1			
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1			
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7	7			
60222230	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	1	1			
60223700	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1			
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5			
60224439	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	1	1			
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3			
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	17	17			
60237460	INLETS, TYPE A, TYPE 23 FRAME AND GRATE	EACH	15	15			
60259330	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	1	1			
60260100	INLETS TO BE ADJUSTED	EACH	2	2			
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	16	16			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	17	17			
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	4	4			
60500040	REMOVING MANHOLES	EACH	1	1			
60500050	REMOVING CATCH BASINS	EACH	34	34			
60500060	REMOVING INLETS	EACH	19	19			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	8,670	8,670			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9			

\* SPECIALTY ITEM

FILE NAME = 4185.800-011.dwg

USER NAME = PAUL SWATEK

DESIGNED - BVS

REVISED -

DRAWN - PJS

REVISED -

PLOT SCALE = 1" = 0833'

CHECKED - KLB

REVISED -

PLOT DATE = 10/17/2012

DATE - 10/17/12

REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
KENSINGTON ROAD IMPROVEMENTS**

SCALE: N.T.S.

SHEET NO. OF SHEETS STA. TO STA.

FAU  
RTE

1295

SECTION

09-00154-00-PV

COUNTY

COOK

TOTAL SHEETS

119

SHEET NO.

07

CONTRACT #: 63746

ILLINOIS FED. AID. PROJECT