

PLAN  
 SURVEYED  
 PLOTTED  
 ALIGNED  
 CHECKED  
 NO. \_\_\_\_\_  
 DATE \_\_\_\_\_  
 BY \_\_\_\_\_

PROFILE  
 SURVEYED  
 PLOTTED  
 REVISIONS  
 CHECKED  
 NO. \_\_\_\_\_  
 DATE \_\_\_\_\_  
 BY \_\_\_\_\_

PAY ITEM #	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0004	0021	0031	0042	0044
60500060	REMOVING INLETS	EACH	6					6
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	210	210				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,015	1,015				
63200310	GUARDRAIL REMOVAL	FOOT	524	524				
67100100	MOBILIZATION	L SUM	1	1				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	37,152	37,152				
* 70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	557	557				
* 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	47,040	47,040				
* 70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	1,949	1,949				
* 70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	420	420				
* 70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	110	110				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	12,640	12,640				
* 72000100	SIGN PANEL - TYPE 1	SQ FT	70	70				
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	103	103				
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	48	48				
* 72900100	METAL POST - TYPE A	FOOT	27	27				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	957	957				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	25,685	25,685				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,484	3,484				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	974	974				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	281	281				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	321	321				
* 78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	488	488				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	7,815	7,815				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	732	732				
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1	1				
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	2,266	2,266				
* 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	53	53				
* 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	108	108				
* 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	187	187				

\* = SPECIALTY ITEM

PAY ITEM #	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0004	0021	0031	0042	0044
* 81400100	HANDHOLE	EACH	4		4			
* 81400200	HEAVY-DUTY HANDHOLE	EACH	6		6			
* 81400300	DOUBLE HANDHOLE	EACH	1		1			
* 81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	56		56			
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	1		1			
* 83006300	LIGHT POLE, ALUMINUM, 30 FT. M.H., 8 FT. MAST ARM	EACH	1		1			
* 83600352	LIGHT POLE FOUNDATION, METAL, 11 1/2" BOLT CIRCLE, 8 5/8" X 6"	EACH	1		1			
* 84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	1		1			
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	1		1			
* 85000300	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	L SUM	1		1			
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1			
* 85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1		1			
* 86000100	MASTER CONTROLLER	EACH	1		1			
* 86400100	TRANSCIVER - FIBER OPTIC	EACH	2		2			
* 87300010	GROUNDING EXISTING HANDHOLE FRAME AND COVER	EACH	8		8			
* 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	2,011		2,011			
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	867		867			
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,187		1,187			
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,118		1,118			
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	679		679			
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1,134		1,134			
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	129		129			
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1,179		1,179			
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		2			
* 87602000	PEDESTRIAN PUSH-BUTTON POST	EACH	4		4			
* 87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1		1			
* 87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1		1			
* 87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1		1			
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	24		24			
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4			
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	35		35			

FILE NAME =  
 Summary of Quantities.dwg

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

Palatine Road Widening STP Project  
 Summary of Quantities

F.A.U. RTE. 1285	SECTION 09-00082-00-CH	COUNTY Cook	TOTAL SHEETS 97	SHEET NO. 4
CONTRACT NO. 63749			ILLINOIS FED. AID PROJECT CMM 9003(492)	

SCALE: NTS SHEET NO. 2 OF 3 SHEETS STA. TO STA.