

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				ROADWAY 0004	SAFETY 0021	NON PARTICIPATING
* XX008188	SANITARY SEWER REPAIR, REMOVE AND REPLACE	FOOT	98	-	-	98
* XX008296	GATE VALVE 10" WITH VAULT, 5' DIAMETER	EACH	9	-	-	9
* XX008789	REMOVE EXISTING HANDHOLE, LIGHTING	EACH	6	-	6	-
* XX008790	WATER MAIN, (RESTRAINED JOINT TYPE) 6"	FOOT	45	-	-	45
* XX008791	WATER MAIN, (RESTRAINED JOINT TYPE) 8"	FOOT	45	-	-	45
* XX008792	WATER MAIN, (RESTRAINED JOINT TYPE) 10"	FOOT	530	-	-	530
* XX008793	WATER MAIN - HDD METHOD, (RESTRAINED JOINT TYPE) 8"	FOOT	60	-	-	60
* XX008794	WATER MAIN - HDD METHOD, (RESTRAINED JOINT TYPE) 10"	FOOT	195	-	-	195
* XX008795	WATER MAIN INSIDE CASING PIPE, 8"	FOOT	23	-	-	23
* XX008796	CASING PIPE, 16"	FOOT	23	-	-	23
* XX008797	WATER MAIN TREE TUNNELING, 10"	FOOT	40	-	-	40
* XX008798	CONNECTION TO EXISTING WATER MAINS (NON-PRESSURE) - 10"	EACH	10	-	-	10
* X5630710	CONNECTION TO EXISTING WATER MAIN, 10"	EACH	1	-	-	1
* XX008799	WATER SERVICE LINE 1 -1/2"	EACH	2	-	-	2
* XX008530	WATER SERVICE LINE, DIRECTIONAL BORING, 1 -1/2"	EACH	1	-	-	1
* XX007821	WATER SERVICE LINE 2"	EACH	1	-	-	1
* XX008801	WATER SERVICE LINE, DIRECTIONAL BORING 2"	EACH	1	-	-	1
* XX008800	GATE VALVE 6" WITH VAULT, 5' DIAMETER	EACH	1	-	-	1
* XX008802	INSERTION VALVE 10" WITH VAULT	EACH	1	-	-	1
* XX008803	INSERTION VALVE 10" WITH VALVE BOX	EACH	1	-	-	1
* XX008804	WATER MAIN CUT-IN TEE, 10"	EACH	4	-	-	4
* XX008805	EXISTING TEE REMOVAL, 10"	EACH	3	-	-	3
* XX008806	ABANDON EXISTING WATER MAIN, FILL WITH CLSM, 8"	FOOT	165	-	-	165
* XX008807	ABANDON EXISTING WATER MAIN, FILL WITH CLSM, 10"	FOOT	337	-	-	337
* XX008808	STEEL CASING REMOVAL, 20 INCH	FOOT	12	-	-	12
* 66901000	BACKFILL PLUGS	CU YD	5	5	-	-
* 72000200	SIGN PANEL - TYPE 2	SQ FT	33	-	33	-
* Z0004002	BOLLARDS	EACH	5	5	-	-
* X0301828	ENGINEERED BARRIER	SQ YD	20	20	-	-

* INDICATES SPECIALTY ITEM

CONSULTANT: BAXTER WOODMAN INC. 12/19/2012
 STATE OF ILLINOIS PROFESSIONAL ENGINEER EXAM
 LICENSE NO. 034-0012, EXPIRES 4/30/2011
 PROJECT: 0348-1352-06-CH
 FILE: 110025-12-500.shp



DESIGNED - DSH	REVISED - 10-12-12 PER IDOT
DRAWN - MAC	REVISED - 10-29-12 PER VILLAGE
CHECKED - TLH	REVISED - 12-19-12 ADDENDUM 1
DATE - 8/23/12	FILE - 110025-12-500.shp

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: STA. TO STA.

F.A.P./F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0348/1352	05-0016C-00-CH	COOK	09	11
C-91-070-06			CONTRACT NO. 63756	
FED. ROAD DIST. NO. 1 (ILLINOIS)			FED. AID PROJECT #-0348/1352	