



INTERCONNECT SCHEDULE OF QUANTITIES

PAY ITEM	UNIT	QNTY.
UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	472
HANDHOLE	EACH	1
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	2386
REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	926
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	2432
REMOVE FIBER OPTIC CABLE FROM CONDUIT	FOOT	937
OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1



USER NAME = brd	DESIGNED - BRD	REVISED -
	DRAWN - OJT	REVISED -
PLOT SCALE = 50,000' / 1" =	CHECKED - JJE	REVISED -
PLOT DATE = 11/20/2012	DATE - 10/22/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERCONNECT SCHEMATIC
IL ROUTE 31 (BATAVIA AV.) TO IL ROUTE 25 (WASHINGTON ST.)

NOT TO SCALE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1441	12-00073-01-TL	KANE	88	47
CONTRACT NO. 63763				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				