

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0021	0031	0042	0044	0021			
				ROADWAY	SAFETY	LANDSCAPING	TRAINEES	OTHER	TRAFFIC SIGNALS			
									31ST STREET AT GOLFVIEW ROAD	IL ROUTE 111 AT GOLFVIEW ROAD	INTERCONNECT	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	300			300						
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	102			102						
20101700	SUPPLEMENTAL WATERING	UNIT	5			5						
20200100	EARTH EXCAVATION	CU YD	9485	9485								
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	55	55								
20400800	FURNISHED EXCAVATION	CU YD	100	100								
20800150	TRENCH BACKFILL	CU YD	690	690								
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	970	970								
Δ 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	100	100								
Δ 21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	180			180						
Δ 25000210	SEEDING, CLASS 2A	ACRE	1.5			1.5						
Δ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	104			104						
Δ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	104			104						
Δ 25100630	EROSION CONTROL BLANKET	SQ YD	6924	6924								
Δ 25200110	SODDING, SALT TOLERANT	SQ YD	500			500						
Δ 25200200	SUPPLEMENTAL WATERING	UNIT	10	10								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	143	143								
28000400	PERIMETER EROSION BARRIER	FOOT	2372	2372								
28000510	INLET FILTERS	EACH	54	54								
28100107	STONE RIPRAP CLASS A4	SQ YD	4	4								
28200200	FILTER FABRIC	SQ YD	681	681								
* 30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	55	55								
* 30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	5189	5189								
31101800	SUBBASE GRANULAR MATERIAL, TYPE B 10"	SQ YD	12501	12501								
35501287	HOT-MIX ASPHALT BASE COURSE, 2 1/4"	SQ YD	2203	2203								
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	91	91								

• REQUIRES SPECIAL PROVISION
Δ INDICATES SPECIALTY ITEM