

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0021	0031	0042	0044	0021			
				ROADWAY	SAFETY	LANDSCAPING	TRAINEES	OTHER	TRAFFIC SIGNALS			
									31ST STREET AT GOLFVIEW ROAD	IL ROUTE 171 AT GOLFVIEW ROAD	INTERCONNECT ROAD	
Δ 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	6799		6799							
Δ 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	1787		1787							
Δ 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	374		374							
Δ 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	12		12							
Δ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	179		179							
Δ 78300100	PAVEMENT MARKING REMOVAL	SQ FT	2076		2076							
Δ 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1		1							
Δ * 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1							1		
Δ 80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	2							1	1	
Δ 81028170	UNDERGROUND CONDUIT, GALVANIZED STEEL 1" DIA.	FOOT	2200		2200							
Δ 81028180	UNDERGROUND CONDUIT, GALVANIZED STEEL 1 1/4" DIA.	FOOT	2000		2000							
Δ 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL 2" DIA.	FOOT	2931							770	1856	305
Δ 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL 2 1/2" DIA.	FOOT	302							77	225	
Δ 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	1087		950					116	21	
Δ 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	607							289	318	
Δ 81028260	UNDERGROUND CONDUIT, GALVANIZED STEEL, 6" DIA.	FOOT	150		150							
Δ 81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	300		300							
Δ 81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	30		30							
Δ 81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	1511		1400	111						
Δ 81100200	CONDUIT ATTACHED TO STRUCTURE, 3/4" DIA., GALVANIZED STEEL	FOOT	600		600							
Δ 81300100	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 4" X 4" X 3"	EACH	17		17							
Δ 81300420	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 10" X 8" X 6"	EACH	1		1							
Δ 81302000	JUNCTION BOX, CAST IRON, ATTACHED TO STRUCTURE, 4" X 4" X 3"	EACH	22		22							
Δ 81400100	HANDHOLE	EACH	15							4	11	
Δ 81400200	HEAVY-DUTY HANDHOLE	EACH	2							2		
Δ 81400300	DOUBLE HANDHOLE	EACH	3							2	1	

• REQUIRES SPECIAL PROVISION
Δ INDICATES SPECIALTY ITEM

FILE NAME = ...N02-Sum quant\2363.500.05.dgn	USER NAME = cte	DESIGNED - DTE	REVISIONS -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U. RTE. 3794	SECTION 12-F3000-23-PK	COUNTY COOK	TOTAL SHEETS 133	SHEET NO. 8
PLOT SCALE = 1,0000' / in.	CHECKED - GAB	DATE - 10/22/2012	REVISIONS -		SCALE: NONE	SHEET NO. 5 OF 11 SHEETS	STA.	TO STA.	CONTRACT NO. 63764				
PLOT DATE = 11/28/2012	DATE - 10/22/2012	REVISIONS -	REVISIONS -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT								