STATION		HOT-MIX ASPHALT BASE COURSE, 2 1/4"	BITUMINOUS MATERIALS (PRIME COAT)	LEVELING BINDER (MACHINE METHOD), N50	LEVELING BINDER (MACHINE METHOD), N70	HOT-MIX ASPHALT SURFACE CSE, MIX "D", N50	HOT-MIX ASPHALT SURFACE CSE, MIX "D", N70	HOT-MIX ASPHALT PAVEMENT, (FULL-DEPTH), 6 3/4"	HOT-MIX ASPHALT PAVEMENT, (FULL-DEPTH), 9"	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	AGGREGATE SUBGRADE IMPROVEMENT 12"	SUB-BASE GRANULAR MATERIAL TYPE B 10 INCH	AGGREGATE SUBGRADE IMPROVEMENT
		35501287	40600100	40600625	40600635	40603335	40603340	40701816	40701861	42000401	30300112	31101800	30300001
		(SQ YD)	(GALLON)	(TON)	(TON)	(TON)	(TON)	(SQYD)	(SQYD)	(SQYD)	(SQYD)	(SQYD)	(CUYD)
31ST STREET	207+06 TO 211+00	0	0	0	0	0	0	0	2041	0	2267	0	0
	211+00 TO 216+00	0	1046	0	117	0	312	0	448	208	1060	0	55
GOLFVIEW ROAD	11+25 TO 16+00	0	173	0	0	52	0	307	0	0	440	561	0
	16+00 TO 21+50	0	319	36	0	96	0	220	0	0	249	0	0
	21+50 TO 26+14.88	0	172	19	0	52	0	901	0	0	1173	0	0
ZOO NORTH LOT	100+70 TO 105+00	535	1589	0	0	475	0	0	0	0	0	4361	0
	105+00 TO 110+50	1104	3292	0	0	981	0	0	0	0	0	3737	0
	110+50 TO 113+70.87	564	1676	0	0	501	0	0	0	0	0	3898	0
	TOTALS	2203	8267	55	117	2157	312	1428	2489	208	5189	12501	55

STATION		CONCRETE CURB, TYPE B	COMB. CONC. C&G,TYPE B-6.12	COMB. CONC. C&G,TYPE B-6.24	CONC. MEDIAN SURFACE, 4 INCH	CONC. MEDIAN TYPE SB-6.06	CONC. MEDIAN TYPE SB-6.12	PCC SIDEWALK, 5 INCH	HMA DRIVEWAY PAVEMENT 6 INCH
		60600605	60603800	60605000	60618300	60619200	60619600	42400200	Z0004522
		(FOOT)	(FOOT)	(FOOT)	(SQFT)	(SQFT)	(SQFT)	(SQFT)	(SQYD)
31ST STREET	207+06 TO 211+00	0	913	0	0	0	0	63	211
	211+00 TO 216+00	30	908	430	0	0	0	4220	59
GOLFVIEW ROAD	11+25 TO 16+00	0	661	0	270	0	316	0	0
	16+00 TO 21+50	0	340	0	0	0	0	0	0
	21+50 TO 26+14.88	0	520	448	0	0	0	0	0
ZOO NORTH LOT	100+70 TO 105+00	0	836	0	0	0	1664	0	0
	105+00 TO 110+50	66	1156	0	405	0	1224	0	0
	110+50 TO 113+70.87	315	396	0	1377	404	0	0	0
	TOTALS	411	5730	878	2052	404	3204	4283	270

STATION		THERMOPLASTIC PAVT. MARKING-LETTERS & SYMBOLS	THERMOPLASTIC PAVT. MARKING-LINE 4"	THERMOPLASTIC PAVT. MARKING-LINE 6"	THERMOPLASTIC PAVT. MARKING-LINE 12"	THERMOPLASTIC PAVT. MARKING-LINE 24"	PAINT PAVEMENT MARKING-LETTERS & SYMBOLS	PAINT PAVEMENT MARKING- LINE 4"	PAINT PAVEMENT MARKING- LINE 6"	PAINT PAVEMENT MARKING- LINE 12"	PAINT PAVEMENT MARKING- LINE 24"	RAISED REFELCTIVE PAVEMENT MARKING
		78000100	78000200	78000400	78000600	78000650	78001100	78001110	78001130	78001150	78001180	78100100
		(SQFT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQFT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)
31ST STREET	207+26 TO 216+00	36	3568	330	151	81	0	0	0	0	0	75
GOLFVIEW ROAD	10+58 TO 26+14.88	364	2606	1658	251	72	0	0	0	0	0	42
ZOO NORTH LOT	100+70 TO 113+70.87	0	0	0	0	0	73	6799	1787	374	12	0
*EXISTING MARKINGS REPLACEMENT		0	1852	0	0	0	0	0	0	0	0	62
	TOTALS	400	8026	1988	402	153	73	6799	1787	374	12	179

FILE NAME = ...\04-Schedules\2563_SCH_01.dgn	USER NAME = dtc	DESIGNED - DTE	REVISED -
		DRAWN - DTE	REVISED -
	PLOT SCALE = 1.0000 ' / in.	CHECKED - GAB	REVISED -
	PLOT DATE = 11/28/2012	DATE - 10/22/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE | SHEET NO. 1 OF 3 SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3784	12-F3000-23-PK	COOK	133	18

CONTRACT NO. 63764

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT