

STATION	CLASS D PATCHES, TYPE IV, 10"	PAVEMENT MARKING TAPE, TYPE III - LETTERS & SYMBOLS	PAVEMENT MARKING TAPE, TYPE III - 4"	PAVEMENT MARKING TAPE, TYPE III - 6"	PAVEMENT MARKING TAPE, TYPE III - 12"	PAVEMENT MARKING TAPE, TYPE III - 24"	PERIMETER EROSION BARRIER	INLET FILTERS	
	44201771	70300510	70300520	70300540	70300560	70300570	28000400	28000510	
	(SQYD)	(SQFT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	
STAGE I	207+06 TO 216+00	135	0	5424	0	0	46	663	15
	106+75 TO 113+70.87	66	0	0	0	0	0	881	14
STAGE II	207+06 TO 216+00	0	0	3606	0	0	10	261	5
	10+58 TO 26+14.88	0	36.4	1388	299	96	0	0	2
	100+00 TO 110+00	0	0	2197	0	0	12	0	6
STAGE III	207+06 TO 216+00	0	0	6984	0	0	10	0	0
	10+58 TO 26+14.88	0	0	1060	0	0	0	0	0
	100+00 TO 110+00	0	0	670	0	0	0	0	0
STAGE IV	10+58 TO 26+14.88	0	0	572	0	0	0	0	0
	100+00 TO 106+75	0	0	841	0	0	0	0	5
STAGE V	19+10 TO 26+14.88	0	0	0	0	0	0	567	7
TOTALS		201	36.4	22742	299	96	78	2372	54

STATION	SIGN PANEL - TYPE 1	REMOVE SIGN PANEL ASSY - TYPE A	RELOCATE SIGN PANEL ASSY - TYPE A	RELOCATE SIGN PANEL ASSY - TYPE B	RELOCATE SIGN PANEL - TYPE 1	TELESCOPING STEEL SIGN SUPPORT	SIGN AND POST	
	72000100	72400100	72400500	72400600	72400710	72800100	X0326696	
	(SQFT)	(EACH)	(EACH)	(EACH)	(SQFT)	(FOOT)	(EACH)	
31ST STREET	207+26 TO 216+00	9	0	2	3	0	201	0
GOLFVIEW AVENUE	10+58 TO 26+14.88	54.68	1	0	1	16	205	0
ZOO NORTH LOT	100+70 TO 105+00	0.00	0	0	0	0	0	2
	105+00 TO 110+50	10.36	0	0	0	0	0	13
	110+50 TO 113+70.87	5.18	0	0	0	0	0	5
TOTALS		79.22	1	2	4	16	406	20

STATION	SEEDING, CLASS 2A	SEEDING (SPECIAL)	NITROGEN FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	SODDING, SALT TOLERANT	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	TOPSOIL FURNISH AND PLACE, 24"	
	25000210	K1005421	25000400	25000600	25200110	25100630	28000250	21101685	
	(ACRE)	(ACRE)	(POUND)	(POUND)	(SQYD)	(SQYD)	(POUND)	(SQYD)	
31ST STREET	207+26 TO 216+00	0.39	0.00	44.60	44.60	500	1895	39.00	180
GOLFVIEW AVENUE	10+58 TO 26+14.88	0.25	0.01	15.00	15.00	0	1199	25.00	0
ZOO NORTH LOT	100+70 TO 113+70.87	0.79	0.00	47.40	47.40	0	3830	78.87	0
TOTALS		1.43	0.01	107.00	107.00	500	6924	142.87	180
ADJUSTED QUANTITY		1.50	0.25	104	104			143	

		TOPSOIL EXCAVATION					TOTALS BY STATION
STATION TO STATION		STAGE I	STAGE II	STAGE III	STAGE IV	STAGE V	
		(CUYD)	(CUYD)	(CUYD)	(CUYD)	(CUYD)	(CUYD)
31ST STREET	207+06 TO 211+00	64.4	0.0	23.7	0.0	0	88.1
	211+00 TO 216+00	20.5	0.0	76.2	0.0	0	96.7
GOLFVIEW AVENUE	10+50 TO 16+00	0.0	0.0	32.1	2.8	0.0	34.9
	16+00 TO 26+14.88	0.0	0.0	0.0	0.0	117.8	117.8
ZOO NORTH LOT	100+70 TO 107+00	0.0	61.7	24.4	29.2	0.0	115.3
	107+00 TO 113+70.87	702.5	0.0	0.0	0.0	0.0	702.5
TOTALS		787.4	61.7	156.4	32.0	117.8	1155.3*

		TOPSOIL PLACEMENT					TOTALS BY STATION
STATION TO STATION		STAGE I	STAGE II	STAGE III	STAGE IV	STAGE V	
		(CUYD)	(CUYD)	(CUYD)	(CUYD)	(CUYD)	(CUYD)
31ST STREET	207+06 TO 211+00	89.0	---	29.1	---	---	118.1
	211+00 TO 216+00	213.1	---	44.0	---	---	257.1
GOLFVIEW AVENUE	10+50 TO 16+00	---	---	75.3	9.5	---	84.8
	16+00 TO 26+14.88	---	---	0.0	---	123.6	123.6
ZOO NORTH LOT	100+70 TO 107+00	---	93.6	---	30.5	---	124.1
	107+00 TO 113+70.87	261.5	---	---	---	---	261.5
TOTALS		563.6	93.6	148.4	40.0	123.6	969.2*

\* EXCESS TOPSOIL EXCAVATION WILL BE PAID FOR AS EARTH EXCAVATION