



**IL ROUTE 171 (FIRST AVENUE)
AERIALLY SUPPORTED INTERCONNECT CABLE
(NOT TO SCALE)**

TEMPORARY INTERCONNECT NOTES

1. TRANSFER OF EXISTING TO TEMPORARY INTERCONNECT CABLE AND TEMPORARY INTERCONNECT CABLE TO PROPOSED MUST BE COMPLETED IN ONE WORKING DAY DURING NON-PEAK HOURS OR AS DIRECTED BY THE ENGINEER.
2. AFTER THE PROPOSED INTERCONNECT IS TURNED ON AND OPERATING TO THE SATISFACTION OF THE ENGINEER, THE TEMPORARY INTERCONNECT CABLE SHALL BE REMOVED.
3. THE 2" CONDUIT USED FOR THE TEMPORARY INTERCONNECT CABLE SHALL BE REMOVED TO BELOW GRADE AND CAPPED AT THE TIME THE TEMPORARY INTERCONNECT IS REMOVED.
4. THE CONTRACTOR MUST NOTIFY THE IDOT SIGNAL SYSTEM ENGINEER A MINIMUM OF SEVEN WORKING DAYS PRIOR TO THE START OF ANY WORK ON THE TRAFFIC SIGNAL INTERCONNECT.
5. ALL WORK AND MATERIALS INVOLVED IN THE INSTALLATION OF THE TEMPORARY INTERCONNECT AND ESTABLISHING SYSTEM OPERATION TO THE SATISFACTION OF THE ENGINEER AND THE IDOT SIGNAL SYSTEM ENGINEER SHALL BE INCLUDED IN THE PAY ITEM "TEMPORARY TRAFFIC SIGNAL INSTALLATION."

NOTE:
THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

RESTORATION OF WORK AREA.
RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDER, MEDIAN, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SALT TOLERANT SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

	USER NAME = mfb	DESIGNED - BRD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TEMPORARY INTERCONNECT PLAN IL ROUTE 171 (1ST AVENUE) 31ST STREET TO 26TH STREET	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50.0000 1" = 50'	DRAWN - MFB	REVISED -			3784	12-F3000-23-PK	COOK	133	84
PLOT DATE = 12/12/2012	CHECKED - JJE	REVISED -	REVISED -	SCALE: 1" = 50'	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT CONTRACT NO. 63764		