SCHEDULE OF QUANTITIES

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50						40603310
			WIDTH	SQYD	INCHES	TONS
Stage I EB	4159+50.00	4167+00.00	4	333.3	2	37.3
Stage II EB	4159+50.00	4161+00.00	4	66.7	2.0	7.5
Stage III WB	4165+50.00	4167+50.00	4	88.9	2	10.0
Stage IV WB	4160+00.00	4167+00.00	4	311.1	2	34.8
					TOTAL	89.6

HOT-MIX ASPHALT SURFACE REMOVAL, 2"				44000157
			WIDTH	SQYD
Stage I EB	4159+50.00	4167+00.00	4	333.3
Stage II EB	4159+50.00	4161+00.00	4	66.7
Stage III WB	4165+50.00	4167+50.00	4	88.9
Stage IV WB	4160+00.00	4167+00.00	4	311.1
			TOTAL	800

SHOULDER RUMBLE STRIPS, 16 INCH				64200116
				FOOT
EB Median	4159+50.00	4167+00.00		750
EB Outside	4159+50.00	4161+00.00		150
WB Outside	4165+50.00	4167+50.00		200
WB Median	4160+00.00	4167+00.00		700
			TOTAL	1,800

SHORT TERM PAVEMENT MARKING				70300100
STAGE I				FOOT
EASTBOUND				
6" SKIP DASH	4144+50.00	4154+50.00	500	250
4" WHITE	4159+50.00	4167+00.00	750	250
6" SKIP DASH	4167+50.00	4170+00.00	125	63
STAGE II				
EASTBOUND				
4" WHITE	4159+50.00	4164+00.00	450	150
6" SKIP DASH	4164+00.00	4167+00.00	150	75
STAGE III				
WESTBOUND				
6" SKIP DASH	4172+50.00	4182+50.00	500	250
4" WHITE	4163+00.00	4167+50.00	450	150
6" SKIP DASH	4159+50.00	4163+00.00	175	88
STAGE IV				
WESTBOUND				
4" WHITE	4160+00.00	4167+00.00	700	234
6" SKIP DASH	4158+50.00	4159+50.00	50	25
TOTAL				1,535
USE				1,560

WORK ZONE PAVEMENT MARKING REMOVAL					70301000
PAVEMENT MARKING TAPE, TYPE III 4"			70300520		
STAGE I			YELLOW	WHITE	
EASTBOUND					SQ FT
	4144+50.00	4170+00.00		2550	850
	4159+50.00	4167+00.00	750		250
(8" GORE PM)	4168+85.00	4172+00.00		630	210
(8" GORE PM)	4168+85.00	4170+15.00		260	87
(8" CHEVRONS)	4168+85.00	4170+15.00		120	40
STAGE II					
EASTBOUND					
	4144+50.00	4167+00.00	2250		750
(25' SKIP DASH)	4159+50.00	4164+00.00		450	150
	4164+00.00	4167+00.00		150	50
STAGE III					
WESTBOUND					
	4159+00.00	4182+50.00	2350		784
	4163+00.00	4167+50.00		450	150
(25' SKIP DASH)	4159+75.00	4163+00.00		163	54
STAGE IV					
WESTBOUND					
(8" GORE PM)	4157+00.00	4159+00.00		400	134
(8" GORE PM)	4157+50.00	4159+00.00		300	100
(8" CHEVRONS)	4158+00.00	4159+00.00		120	40
	4158+00.00	4182+00.00		2,400	800
	4160+00.00	4167+00.00	700		234
			6,050	7,993	
		TOTAL	14,043		4,683
		USE	14,100		4,700

TEMPORARY CONCRETE BARRIER				70400100
STAGE I				FOOT
4159+83.40	4165+05.74	EB		512.5
			TOTAL	512.5

RELOCATE TEMPORARY CONCRETE BARRIER				70400200
				FOOT
STAGE II	4160+98.31	4165+05.97	EB	400
STAGE III	4161+98.28	4166+00.73	WB	400
STAGE IV	4161+98.05	4166+89.00	WB	487.5
			TOTAL	1287.5

IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3				Z0030250
STAGE I				
4159+83.40	EB			1
			TOTAL	1

IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3				Z0030350
				EACH
STAGE II	4160+98.31	EB		1
STAGE III	4166+00.73	WB		1
STAGE IV	4166+89.00	WB		1
			TOTAL	3

PAVEMENT MARKING REMOVAL				78300100
STAGE I				
EASTBOUND			FOOT	SQ FT
6" SKIP DASH	4144+50.00	4154+50.00	500	250
4" WHITE	4159+50.00	4167+00.00	750	250
6" SKIP DASH	4166+00.00	4170+00.00	275	138
STAGE II				
EASTBOUND				
4" WHITE	4159+50.00	4164+00.00	450	150
6" SKIP DASH	4164+00.00	4167+00.00	150	75
STAGE III				
WESTBOUND				
6" SKIP DASH	4172+50.00	4182+50.00	500	250
4" WHITE	4163+00.00	4167+50.00	450	150
6" SKIP DASH	4159+50.00	4163+00.00	175	88
STAGE IV				
WESTBOUND				
4" WHITE	4160+00.00	4167+00.00	700	234
6" SKIP DASH	4158+50.00	4161+00.00	150	75
			TOTAL	1,660
			USE	1,700

POLYUREA PAVEMENT MARKING TYPE I - LINE 4"			78008210
STAGE I			FOOT
EASTBOUND	4159+50.00	4167+00.00	750
STAGE II			
EASTBOUND	4159+50.00	4164+00.00	450
STAGE III			
WESTBOUND	4163+00.00	4167+50.00	450
STAGE IV			
WESTBOUND	4160+00.00	4167+00.00	700
TOTAL			2,350

POLYUREA PAVEMENT MARKING TYPE I - LINE 6"			78008230
STAGE I			FOOT
EASTBOUND	4144+50.00	4154+50.00	500
EASTBOUND	4166+00.00	4170+00.00	275
STAGE II			
EASTBOUND	4164+00.00	4167+00.00	150
STAGE III			
WESTBOUND	4172+50.00	4182+50.00	500
WESTBOUND	4159+50.00	4163+00.00	175
STAGE IV			
WESTBOUND	4158+50.00	4161+00.00	150
TOTAL			1,750

REPLACEMENT REFLECTOR			78100300
EASTBOUND			EACH
SKIP-DASH	4144+50.00	4154+50.00	22
WESTBOUND			
SKIP-DASH	4172+50.00	4182+50.00	22
		TOTAL	44

FINAL SURVEY			
NOTE BOOK	SURVEYED	BY	DATE
	PLOTTED		
	TABULATED		
	AREAS CHECKED		
NO.			

ORIGINAL SURVEY			
NOTE BOOK	SURVEYED	BY	DATE
	PLOTTED		
	TABULATED		
	AREAS CHECKED		
NO.			

FILE NAME = 0264J27-sht-schedule.dgn
PLOT DATE = 8/29/2012
PLOT SCALE = 50.0000 ' / IN.

CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED	G.F.L./K.R.K.	REVISED	-
DRAWN	K.R.K.	REVISED	-
CHECKED	E.L.M.	REVISED	-
DATE	JULY 2012	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
I-39 OVER I-88

SCALE: NONE | SHEET NO. 1 OF 1 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	02 BRIDGE PAINTING 2013-2	OGLE	26	5
		CONTRACT NO. 64J27		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		