

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(1-1)R	KENDALL	514	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	UNIT	TOTAL QUANTITY	URBAN												
				FEDERAL = 80% STATE = 20%	FEDERAL = 80% STATE = 10% COUNTY = 5% VILLAGE = 5%	FEDERAL = 80% STATE = 13.4% COUNTY = 0% VILLAGE = 6.6%	FEDERAL = 80% STATE = 10% COUNTY = 0% VILLAGE = 10%	FEDERAL = 80% STATE = 0% COUNTY = 10% VILLAGE = 10%	VILLAGE = 100%	VILLAGE = 100%	COUNTY = 50% VILLAGE = 50%	VILLAGE - 100%	FEDERAL = 80% VILLAGE = 20%	VILLAGE = 100%	VILLAGE = 100%	
				ROADWAY	ORCHARD / MINKLER TRAFFIC SIGNALS	DOUGLAS STREET TRAFFIC SIGNALS	FOREST AVENUE TRAFFIC SIGNALS	WASHINGTON / PLAINFIELD TRAFFIC SIGNALS	GROVE / PLAINFIELD TRAFFIC SIGNALS	SCHOOL ENTRANCE TRAFFIC SIGNALS	HIGHWAY LIGHTING	HIGHWAY LIGHTING GROVE ROAD	EMERGENCY VEHICLE PREEMPTION	SIDEWALK & BIKE PATH	QUARRY ENTRANCE	UTILITIES
				0003	0021					0021		0021	0028	0003	0043	
60600605	CONCRETE CURB, TYPE B	FOOT	142	142												
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2221	2221												
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	80	80												
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	37038	37038												
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	30	30												
60609100	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 (VARIABLE WIDTH GUTTER FLAG)	FOOT	49	49												
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	29111	29111												
60618740	CONCRETE MEDIAN, TYPE M-2.12	SQ FT	75364	75364												
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2												
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2	2												
* 63200310	GUARDRAIL REMOVAL	FOOT	130	130												
* 63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1178	1178												
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1600	1600												
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1												
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	6	6												
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24												
67100100	MOBILIZATION	L SUM	1	1												
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	314	314												
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	52	50			2									
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1												
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	3464	3464												
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	370141	370141												
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	2724	2724												
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	1200	1200												
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	150000	150000												
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	1000	1000												
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	122121	122121												
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1188	1188												
* 72000100	SIGN PANEL - TYPE 1	SQ FT	1832	1301		38	14	38	38	23				180		
* 72000200	SIGN PANEL - TYPE 2	SQ FT	651	438		50	25	23	60	55						

I:\PROJECTS\66420\66420_SUMMARY_OF_QUANTITIES.dgn
 FILE NAME = PAC\LOCAL\DDT\DIST\CONTRACT\Phase II\SUMMARY OF QUANTITIES.dgn

* DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY SJF
 HORIZ. CHECKED BY MED
 DATE 7/18/2012