

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(1-1)R	KENDALL	514	33
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

JOINT USE PATH SCHEDULE

STATION	TO STATION	OFFSET	AGGREGATE BASE COURSE, TYPE A 6" (SQ YD)	BIT. MATERIALS (PRIME COAT) (GAL)	INCIDENTAL HOT MIX ASPHALT (TON)
838+79.55	842+30.02	RT.	384.9	144.3	43.1
843+58.11	846+00.00	RT.	268.1	100.5	30.0
846+00.00	858+00.00	RT.	1,341.4	503.0	150.2
858+00.00	862+61.02	RT.	522.4	195.9	58.5
863+74.29	873+00.00	RT.	1,043.7	391.4	116.9
873+00.00	876+15.05	RT.	355.8	133.4	39.9
876+94.76	879+30.29	RT.	273.9	102.7	30.7
881+24.11	882+22.12	RT.	114.3	42.9	12.8
882+43.84	883+53.39	RT.	123.5	46.3	13.8
884+11.08	885+57.07	RT.	165.0	61.9	18.5
885+68.87	887+58.29	RT.	214.4	80.4	24.0
887+68.15	888+00.00	RT.	36.1	13.5	4.0
888+00.00	889+75.64	RT.	197.7	74.2	22.1
890+28.53	891+69.56	RT.	158.5	59.5	17.8
892+22.08	896+70.51	RT.	498.7	187.0	55.9
897+57.23	903+00.00	RT.	603.4	226.3	67.6
903+00.00	909+77.81	RT.	753.6	282.6	84.4
911+07.19	918+00.00	RT.	770.8	289.1	86.3
918+00.00	918+45.39	RT.	50.4	18.9	5.8
TOTALS			7,876.7	2,953.8	882.2

DETECTABLE WARNINGS (SPECIAL)

STATION	LT/RT	LENGTH	WIDTH	0003(80/20)		0028(50/50)		ROUTE	COMMENTS
				SQ FT	SQ FT	SQ FT	SQ FT		
838+67	LT	8.8	2.0			17.6		IL ROUTE 71	
838+67	RT	6.0	2.0			12.0		IL ROUTE 71	
842+39	RT	16.5	2.0			33.0		IL ROUTE 71	
843+44	RT	17.4	2.0			34.8		IL ROUTE 71	
862+74	LT	6.1	2.0			12.2		IL ROUTE 71	
862+75	RT	6.9	2.0			13.8		IL ROUTE 71	
876+08	LT	10.0	2.0	20.0				IL ROUTE 71	
876+89	LT	9.9	2.0			19.8		IL ROUTE 71	
879+49	RT	10.0	2.0	20.0				IL ROUTE 71	
879+61	RT	6.0	2.0	12.0				IL ROUTE 71	ON ISLAND
879+61	LT	5.7	2.0			11.4		IL ROUTE 71	
879+66	RT	10.0	2.0	20.0				IL ROUTE 71	ON ISLAND
879+77	RT	10.0	2.0	20.0				IL ROUTE 71	ON ISLAND
880+62	RT	10.0	2.0	20.0				IL ROUTE 71	ON ISLAND
880+83	RT	10.3	2.0	20.6				IL ROUTE 71	ON ISLAND
880+85	RT	6.0	2.0	12.0				IL ROUTE 71	ON ISLAND
880+87	LT	5.2	2.0			10.4		IL ROUTE 71	
881+11	RT	22.1	2.0	44.2				IL ROUTE 71	
883+64	RT	13.3	2.0	26.6				IL ROUTE 71	
884+01	RT	13.2	2.0	26.4				IL ROUTE 71	
896+82	RT	15.5	2.0	31.0				IL ROUTE 71	
896+86	LT	5.8	2.0			11.6		IL ROUTE 71	
897+41	LT	7.2	2.0			14.4		IL ROUTE 71	
897+47	RT	11.9	2.0	23.8				IL ROUTE 71	
900+97	LT	6.5	2.0	13.0				IL ROUTE 71	
901+48	LT	6.5	2.0	13.0				IL ROUTE 71	
909+88	LT	5.0	2.0	10.0				IL ROUTE 71	
909+90	RT	19.0	2.0	38.0				IL ROUTE 71	
910+76	RT	15.1	2.0			30.2		IL ROUTE 71	
910+84	LT	10.2	2.0	20.4				IL ROUTE 71	
910+98	LT	5.0	2.0	10.0				IL ROUTE 71	
910+98	RT	5.3	2.0			10.6		IL ROUTE 71	
49+28	LT	11.3	2.0	22.6				FOREST	
49+50	RT	17.0	2.0			34.0		FOREST	
50+51	LT	7.2	2.0	14.4				FOREST	
50+72	RT	5.9	2.0			11.8		FOREST	
194+16	LT	12.2	2.0	24.4				WASHINGTON/PLAINFIELD	
195+22	LT	12.2	2.0	24.4				WASHINGTON/PLAINFIELD	
200+88	LT	5.6	2.0			11.2		WASHINGTON/PLAINFIELD	
200+88	RT	5.1	2.0	10.2				WASHINGTON/PLAINFIELD	
TOTAL				497.0		288.8			

TEMPORARY FENCE

ROUTE	STATION	TO	STATION	LENGTH (FEET)
IL 71	788+40 LT		788+55 LT	15.0
IL 71	804+90 LT		805+70 LT	80.0
IL 71	806+35 LT		807+10 LT	75.0
IL 71	810+40 LT		810+60 LT	20.0
IL 71	810+90 LT		811+20 LT	30.0
IL 71	831+40 LT		831+60 LT	20.0
IL 71	832+30 LT		833+95 LT	165.0
IL 71	835+90 LT		836+35 LT	45.0
IL 71	841+90 LT		842+65 LT	75.0
IL 71	847+45 LT		849+35 LT	190.0
IL 71	887+79 RT		889+75 RT	196.0
IL 71	890+35 RT		891+71 RT	136.0
DOUGLAS	101+65 LT		101+80 LT	15.0
DOUGLAS	103+85 RT		105+95 RT	210.0
FOREST	48+75 LT		49+15 LT	40.0
TOTAL				1312.0

TREE TRUNK PROTECTION

STATION	OFFSET	SIZE (IN)	EACH	ROUTE
841+12	52' LT	6	1	IL 71
842+53	88' RT	8	1	IL 71
844+58	51' LT		1	IL 71
877+97	73' RT		1	IL 71
912+40	61' LT		1	IL 71
67+90	112' LT	31	1	ORCHARD
68+55	108' LT	25	1	ORCHARD
197+13	65' LT	12	1	WASHINGTON/PLAINFIELD
TOTAL				8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ. DATE 7/5/2012

DRAWN BY: SJF CHECKED BY: MED

TUG PROJ: 3102014
 PLDT DATE: 7/5/2012
 FILE NAME: p:\civil\11111111.dwg