

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3:1	(1-11R)	KENDALI	514	37
STA.	TO STA.			
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

ROADWAY REMOVAL

STATION	TO	STATION	PAVEMENT REMOVAL AREA (SQ YD)	DRIVEWAY PAVEMENT REMOVAL AREA (SQ YD)	SIDEWALK REMOVAL AREA (SQ FT)	COMBINATION CURB AND GUTTER REMOVAL LENGTH (FEET)	PAVED SHOULDER REMOVAL AREA (SQ YD)	COMMENT
780+44.9		787+00.0	1815.5					
783+64.7	LT	785+61.8		395.8				
784+93.7	RT	785+64.7		40.5				
787+00.0		801+00.0	6343.1					
789+28.2	LT	789+98.4		273.1				BUELL RD
792+70.1	LT	793+45.2		201.7				HERRENS LANE
801+00.0		816+00.0	4961.2					
802+06.3	LT	802+75.6		113.8				
802+10.6	RT	802+37.7		21.0				
803+82.1	LT	804+22.1		141.2				
803+87.5	RT	804+14.8		18.8				
812+52.5	RT	813+69.9		417.2				
816+00.0		831+00.0	4168.8					
823+01.5	LT	823+75.3		125.4				
824+78.5	LT	825+40.3		38.9				
826+87.2	LT	827+50.0		95.0				
827+50.0	LT	827+92.7		38.6				
829+04.3	LT	829+74.4		55.7				
830+77.5	LT	831+36.3		114.2				
831+00.0		846+00.0	5125.5					
831+36.6	LT	832+27.4		165.5				
832+63.4	RT	832+93.8		17.6				
833+80.6	LT	835+05.4		453.7				MAIN ST
842+18.1	RT	843+74.3		610.3				PARADISE PARKWAY
842+18.1	RT	842+70.7			278.0	126.0		PARADISE PARKWAY
842+58.6	LT							PARADISE PARKWAY
843+21.1	RT	843+74.3				127.6		PARADISE PARKWAY
843+33.2	LT				300.3			PARADISE PARKWAY
846+00.0		858+00.0	3823.4					
850+84.5	LT	851+58.9		196.1				
853+87.3	LT	855+06.0		242.8				
857+55.0	LT	858+15.0		163.1				
858+00.0		873+00.0	4136.5					
873+00.0		888+00.0	5593.7					
875+79.1	LT	877+20.2		413.9				
875+79.7	RT	877+18.8		457.7				
875+81.0	RT	876+20.7			97.9			
875+91.0	LT	876+29.1			70.9			
876+11.0	LT	876+21.5				104.4		
876+66.8	RT	877+15.8			105.9			
876+67.8	LT	877+11.9			77.3			
880+66.4	RT	882+23.7			874.1			
881+38.2	LT	881+72.5		440.6				
882+14.4	RT	882+71.6		107.4				
882+45.0	RT	883+75.4			677.8			
882+87.4	LT	883+74.9		331.9				
883+53.2	RT	884+11.5	180.1					CALUMET ST
883+74.9	LT	884+13.5		173.2				
883+92.8	RT	885+52.8			777.6			
884+91.2	LT	885+43.0		205.1				
885+11.4	RT	885+61.5		81.2				
885+61.9	RT	887+58.6			990.2			
886+70.9	LT	887+27.4		370.9				
887+54.9	RT	887+78.3		70.4				
887+69.0	RT	888+00.0			151.3			
888+00.0	RT	889+86.7			965.2			
888+00.0		903+00.0	6188.4					
889+57.8	RT	890+46.2				88.9		
889+76.5	RT	890+27.2		150.1				
890+17.6	RT	891+84.5			870.6			

ROADWAY REMOVAL

STATION	TO	STATION	PAVEMENT REMOVAL AREA (SQ YD)	DRIVEWAY PAVEMENT REMOVAL AREA (SQ YD)	SIDEWALK REMOVAL AREA (SQ FT)	COMBINATION CURB AND GUTTER REMOVAL LENGTH (FEET)	PAVED SHOULDER REMOVAL AREA (SQ YD)	COMMENT
891+31.8	LT	896+88.6					227.3	
891+32.2	RT	891+83.3					15.6	
891+66.9	RT	892+24.3		141.9				
892+07.8	RT	896+80.5			2342.4			
892+07.2	RT	896+59.2					186.0	
897+48.2	RT	903+00.0			2623.1			
897+04.0	LT	897+72.6					46.8	
897+09.0	LT	897+76.8			533.1			
897+79.2	RT	903+00.0					173.6	
897+94.4	LT	900+89.7					104.5	
896+43.6	LT	898+05.6	842.3					FRANKLIN ST
896+59.2	RT	897+79.2		382.0				
896+59.2	RT	896+96.3				49.0		
897+40.9	RT	897+79.2				57.1		
897+70.5	LT	897+97.9		102.3				
897+91.8	LT	901+06.5			1582.7			
900+89.7	LT	901+08.2				52.7		
900+89.6	LT	901+53.6	204.6					BELL CT
901+36.5	LT	901+53.6				52.0		
901+38.0	LT	903+00.0			903.1			
901+53.6	LT	903+00.0					54.4	
903+00.0	RT	910+00.4			3706.2			
903+00.0	LT	910+18.0			3618.8			
903+00.0		918+00.0	7657.3					
903+00.0	LT	909+39.6					213.2	
903+00.0	RT	909+70.9					260.2	
910+86.0	RT	910+97.3			85.8			
909+85.5	LT	910+98.3		222.0				
909+39.6	LT	910+20.1				101.2		
909+70.9	LT	911+20.1		563.5				
909+70.9	RT	910+14.1				58.0		
910+64.5	LT	910+98.3				40.1		
910+80.5	RT	911+20.2				67.3		
910+71.4	LT	918+00.0			3697.0			
910+98.3	LT	916+93.0					241.6	
911+20.1	RT	915+74.1					230.0	
917+80.2	LT	918+85.9				86.3		
917+81.8	RT	918+85.9				85.7		
918+00.0	LT	918+79.1			410.8			
918+00.0		918+85.9	527.5					
918+51.3	RT	918+76.8		107.0				
ORCHARD / MINKLER								
56+70.0		62+23.1	2428.2					
62+85.9		65+00.0	1501.5					
65+00.0		71+30.0	2436.8					
66+26.3	LT	67+37.5	318.1					BUDLONG RD
TOTAL THIS SHEET			60683	5851	25496	1344	1753	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ. DATE 7/5/2012

DRAWN BY SJF CHECKED BY MED

AUG PROJ. # 100904
 FILE NAME = 7/5/2012
 FILE NAME = p:\proj\100904\100904.dwg