CONTRACT NO. 66420

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(1-1)R	KENDALL	514	44
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STORM SEWER SCHEDULE

PIPE RUN	UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	LENGTH	SLOPE	STORM SEWERS, CLASS A, TYPE 1														STORM SEWERS, CLASS A, TYPE 2															S.S. CLASS A, TYPE 3	STORM SEWER (WATER MAIN REQUIREMENTS)						TRENCH BACKFILL
			FEET	%	12"	12" R.G	15"	15" R.G	18"	24"	24" R.G	27"	30"	30"EQRS	36"	42"	42" R.G	54"	12"	12" R.G	15"	15" R.G	18"	18" R.G	24"	24" R.G	27"	30"	30" R.G	36"	36" R.G	42"	42" R.G	54"	48"	12"	15"	24"	30"	36"	42"	CU YD
192	7-21-MHA5	7-22-CS6	4	0.75																										4												0
193	7-22-CS6	7-22A-MHA7	38.3	0.81																										38.3												0
194	7-22C-MHA6	7-19A-MHA7	21.3	1.13												21.3																										0
194A	30" FES	7-22C-MHA6	8	23.38									8																													0
195	7-19A-MHA7	7-22A-MHA7	87.3	0.79																												87.3										94.8
196	7-19B-CS6	7-19A-MHA7	49.6	0.10																										49.6												0
197	7-23A-MHA5	7-19B-CS6	9.5	0.42																										9.5												0
198	7-25-CS6	7-22A-MHA7	55.2	0.49																					55.2																	0
199	7-22A-MHA7	7-22B-FES	40	0.12																												40										0
200	7-26-MHA5	7-25-CS6	4.2	0.71																					4.2																	0
201	7-24-MHA5	7-26-MHA5	4.7	0.64																					4.7																	0
202	7-23-INA	7-23A-MHA5	5.5	1.82	5.5																																					0.2
203	7-28A-INA	7-28-MHA5	11.8	1.02	11.8																																					0
204	7-28-MHA5	7-24-MHA5	115.7	1.05																					115.7																	73.1
205	7-29-INA	7-29A-MHA5	5.5	1.82	5.5																																					0.3
206	7-29A-MHA5	7-23A-MHA5	115.8	0.46																										115.8												35.3
207	7-30-INA	7-30A-MHA5	5.5	1.82	5.5																																					0.3
208	7-30A-MHA5	7-29A-MHA5	93.5	0.45																										93.5												0
209	7-31-MHA5	7-28-MHA5	92.8	0.55																					92.8																	37.5
210	7-33A-MHA5	7-30A-MHA5	99.6	0.45																										99.6												0
211	7-33-INB	7-33A-MHA5	4.5	0.67																	4.5																					0.4
212	7-34-INB	7-33-INB	68	0.49			68																																			12.7
213	7-37-INB	7-34-INB	102	0.50	102																																					17.4
214	7-36B-CS6	7-33A-MHA5	87.8	0.46																										87.8												0
215	7-36A-MHA5	7-36B-CS6	6.4	0.47																										6.4												0
216	7-36-INA	7-36A-MHA5	5.5	1.82	5.5																																					0.3
217	7-39A-MHA5	7-36A-MHA5	100.1	0.45																										100.1												0
218	7-39-INA	7-39A-MHA5	5.5	1.82	5.5																																					0.3
219	7-42-INA	7-40-INB	13.6	1.25	13.6																																					0
220	7-40-INB	7-37-INB	102	0.50	102																																					15.3
221	7-43A-MHA5	7-39A-MHA5	145	0.45																										145												0
222	7-46-INA	7-44-INB	15.7	0.45	15.7																																					0
223	7-44-INB	7-43-INB	68	0.47																	68																					21.9
224	7-43-INB	7-43A-MHA5	4.5	0.89																	4.5																					0.9
225	7-47A-MHA5	7-43A-MHA5	89.9	0.46																										89.9												0
226	7-47-INA	7-47A-MHA5	5.5	1.82	5.5																																					0.3
227	7-48-INB	7-44-INB	91.6	0.51															91.6																							17.5
228	7-52-INA	7-48-INB	92.5	0.85	92.5																																					15.7
229	7-51A-MHA5	7-47A-MHA5	89.7	0.46																										89.7												0
230	7-50-INA	7-51A-MHA5	23.1	0.61															23.1																							0
231	7-51-INA	7-51A-MHA5	5.5	1.82	5.5																																					0.2
232	7-53A-CS6	7-51A-MHA5	14.9	0.47																										14.9												0
233	7-54A-MHA5	7-53A-CS6	97	0.56																					97																	0
234	7-57-INA	7-55-MHA5	17.2	0.52															17.2																							0
235	7-55-MHA5	7-54-MHA5	68	0.47																					68																	61.4
236	7-54-MHA5	7-54A-MHA5	3	1.00																					3																	0
237	7-58A-MHA5	7-54A-MHA5	94	0.55																					94																	0
238	7-58-INA	7-58A-MHA5	5.5	1.82	5.5																																					0.2
239	7-59-INB	7-55-MHA5	96.7	0.50																			96.7																			61.5
		TOTAL THIS SHEET	381.6		0	0	68	0	0	0	0	0	8	0	0	21.3	0	0	131.9	0	77	0	96.7	0	534.6	0	0	0	0	944.1	0	127.3	0	0	0	0	0	0	0	0	0	467.5

LEGEND

R.G. = RUBBER GASKETED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ.

DATE 7/5/2012

DRAWN BY SJF

CHECKED BY MED

TUE HOUR = 0805614
PLOT DATE = 7/5/2012
FILE NAME = pw:\\civil\...idot.dist3\oswego\phase 1\Schedule*.dgn