CONTRACT NO. 66420

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(1-)R	KENDALL	514	49
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STORM SEWER SCHEDULE

PIPE RUN	UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	LENGTH	SLOPE	STORM SEWERS, CLASS A, TYPE 1														STORM SEWERS, CLASS A, TYPE 2																S.S. CLASS A, TYPE 3	STORM SEWER (WATER MAIN REQUIREMENTS)						TRENCH BACKFILL
			FEET	%	12"	12" R.G	15"	15" R.G	18"	24"	24" R.G	27"	30"	30"EQRS	36"	42"	42" R.G	54"	12"	12" R.G	15"	15" R.G	18"	18" R.G	24"	24" R.G	27"	30"	30" R.G	36"	36" R.G	42"	42" R.G	54"	48"	12"	15"	24"	30"	36"	42"	CU YD
429	11-107-INA	11-108-INB	61	0.38	61																																						8.5
430	11-108-INB	11-106-MHA4	17	0.53															17																								3.7
431	11-109-MHA5	11-54-MHA6	234.7	0.52							234.7																																0
432	11-110-INB	11-109-MHA5	3.8	0.79				3.8																																			0.3
433	11-111-INB	11-110-INB	82.7	0.48				82.7																																			11.6
434	11-112-MHA4	11-109-MHA5	83.9	0.50															83.9																								14.4
435	11-113-INA	11-112-MHA4	5.4	0.56	5.4																																						0.3
436	11-114-INA	11-111-INB	85.5	0.50	85.5																																						3.4
437	12-01-INA	12-02-MHA4	4.6	2.17	4.6																																						0.3
438	12-02-MHA4	12-03-MHA4	211.9	0.75															211.9																								0
439	12-03-MHA4	12-05-MHA4	244.1	0.72																244.1																							0
440	12-04-INA	12-05-MHA4	4.7	6.38															4.7																								0.3
441	12-05-MHA4	12-06-MHA4	128.9	0.70															128.9																								67.2
442	12-06-MHA4	12-07-MHA4	183	0.72																	183																						72.4
443	12-07-MHA4	12-08-MHA5	80.4	0.72																	80.4																						29.7
444	12-08-MHA5	12-10-MHA5	105.4	0.68																					105.4																		0
445	12-09-INA	12-10-MHA5	4.5	2.22															4.5																								0.3
446	12-10-MHA5	12-12-MHA5	129	0.72																					129																		0
447	12-11-INA	12-12-MHA5	4.5	2.22	4.5																																						0.3
448	12-12-MHA5	12-14-MHA5	129	0.71																					129																		0
449	12-13-INA	12-14-MHA5	4.3	2.33	4.3																																						0.3
450	12-14-MHA5	12-16-MHA5	115	0.50																						115																	0
451	12-15-INA	12-16-MHA5	3.5	1.43															3.5																								0.5
452	13-01-INA	13-02-MHA4	19	0.42	19																																						2.9
453	13-02-MHA4	13-03-MHA4	213	0.79	213																																						0
454	13-03-MHA4	13-05-MHA4	223	0.55																	223																						0
455	13-05-MHA4	13-04-MHA4	16	0.56																	16																						2.9
456	13-04-MHA4	13-06-MHA4	192	0.55																	192																						145.9
457	13-06-INA	13-07-MHA4	18	0.56																	18																						2.8
458	13-07-MHA4	13-09-MHA4	211.4	0.78																	211.4																						0
459	13-08-INA	13-09-MHA4	18.5	0.54	18.5																																						2.9
460	13-09-MHA4	13-11-MHA4	186	0.76																	186																						0
461	13-10-INA	13-11-MHA4	19	1.42															19																								3.3
462	13-11-MHA4	13-13-MHA5	185.3	1.15																				185.3																			0
463	13-12-INA	13-13-MHA5	20.7	0.58																20.7																							3.5
464	13-13-MHA5	13-14-MHA5	130.6	0.30																						130.6																	125.8
464A	13-14-MHA5	13-15-MHA5	66.5	0.30																					66.5																		89.4
464B	13-15-MHA5	13-16-MHA5	131.6	0.31																					131.6																		132.8
465	14-01-INA	14-02-MHA4	68.8	0.42	68.8																																						4.7
466	14-02-MHA4	14-03-MHA4	82.1	0.72																															82.1								9.1
467	14-03-MHA4	14-05-MHA4	79.5	0.63																															79.5								6.9
468	14-04-INA	14-05-MHA4	61	0.16	61																																						2.6
469	14-05-MHA4	14-07-MHA5	244.8	0.74																																244.8							29.5
470	14-06-INA	14-07-MHA5	48.6	0.21	48.6																																						2.1
471	14-07-MHA5	14-08-MHA5	38.4	0.49																																		38.4					2.1
		TOTAL THIS SHEET			594.2	0	0	86.5	0	0	234.7	0	0	0	0	0	0	0	473.4	264.8	1109.8	0	0	185.3	561.5	245.6	0	0	0	0	0	0	0	0	0	161.6	244.8	38.4	0	0	0	782.7

LEGEND

R.G. = RUBBER GASKETED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ.

DATE 7/5/2012

DRAWN BY SJF

CHECKED BY MED

TUG PROJ #3195814
PLOT DATE = 7/9/2012
FILE NAME = pw:\\civil_idot.dms3\hosenego\chase 11\Schedule\Adgn