

F.A.P. R.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(1-1) R	KENDALL	54	66
STA.	TO STA.			
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

SCHEDULE OF QUANTITIES

TEMPORARY PAVEMENT SCHEDULE						
STA. TO STA.	LT / RT	TEMPORARY RAMP	TEMPORARY PAVEMENT REMOVAL	TEMPORARY PAVEMENT	HOT-MIX ASPHALT SHOULDERS, 6"	AGGREGATE SHOULDERS, TYPE A
		(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)
PRE-STAGE 1						
IL RTE 71						
805+00	818+00	RT		3,017	3,017	88
818+00	831+00	RT		2,504	2,504	129
831+00	842+48	RT		1,632	1,632	99
AD. SE PKWY ENT						
843+43	845+00	RT		62	62	
846+00	858+00	RT		194	194	22
858+00	863+15	RT		1,655	1,655	103
863+50	873+00	RT		1,542	1,542	44
SIDE OF FOREST						
873+00	879+84	RT		2,465	2,465	75
880+55	889+00	RT		434	434	35
888+00	894+05	RT		2,070	2,070	60
897+79	901+95	RT		1,811	1,811	64
904+66	907+17	RT		710	710	52
911+20	915+09	RT		252	252	36
FOREST AVE						
50+35	51+98	RT		146	146	22
PLAINFIELD RD						
187+00	194+55	RT		322	322	34
194+84	195+85	RT				
GROVE RD						
10+40	13+00	RT				
WASHINGTON ST						
200+41	203+00	RT				
203+00	209+00	RT				
STAGE 1						
IL RTE 71						
805+00	812+50	T & MEDIAN		1,002	1,002	26
850+77	862+71	MEDIAN		242	242	
864+18	870+00	MEDIAN		512	512	
874+02	879+52	MEDIAN		842	842	
903+70	913+21	LT		568	568	56
912+52	917+05	LT		236	236	39
MAIN ST						
52+00	108+06	LT				
FOREST AVE						
46+32	49+26	LT				
50+17	51+89	LT				
52+60	53+10	LT				
PLAINFIELD RD						
188+00	191+25	LT				
195+25	198+00	MEDIAN				
198+00	199+05	MEDIAN				
WASHINGTON ST						
205+10	209+00	LT				

TEMPORARY PAVEMENT SCHEDULE						
STA. TO STA.	LT / RT	TEMPORARY RAMP	TEMPORARY PAVEMENT REMOVAL	TEMPORARY PAVEMENT	HOT-MIX ASPHALT SHOULDERS, 6"	AGGREGATE SHOULDERS, TYPE A
		(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)
STAGE 1A						
MAIN ST						
101+54	105+93	RT		373	373	38
837+70	838+86	LT		98		
FOREST AVE						
880+50		RT		112		
STAGE 1B						
IL RTE 71						
877+50		RT		37		
FOREST AVE						
863+44.48		LT		138		
863+44.48		RT		119		
PLAINFIELD RD						
195+14	195+25	MEDIAN		15	15	
880+24		LT		107		
STAGE 1D						
PLAINFIELD RD						
880+24.08		LT		168		
880+24.08		RT		212		
FOREST AVE						
886+50		RT		39		
STAGE 1E						
IL RTE 71						
883+50		LT		28		
STAGE 2						
IL RTE 71						
807+40	812+48	MEDIAN		545	545	
PLAINFIELD RD						
880+24.08		LT		78		
PRE-STAGE 4						
IL RTE 71						
774+45	787+00	RT		1,549	1,549	106
787+00	797+39	RT		1,438	1,438	89
798+50	801+00	RT		270	270	15
SIDE OF MINI						
801+00	805+00	RT		1,122	1,122	
801+00	805+00	RT		518	518	28
ORCHARD RD						
83+82	85+00	RT		139	139	12
85+00	71+30	RT		555	555	54
STAGE 4						
IL RTE 71						
774+05	787+00	LT		1,588	1,588	111
787+00	788+50	LT		42	42	13
792+00	797+17	MEDIAN		453	453	
805+90	806+40	MEDIAN		74	74	

TEMPORARY PAVEMENT SCHEDULE						
STA. TO STA.	LT / RT	TEMPORARY RAMP	TEMPORARY PAVEMENT REMOVAL	TEMPORARY PAVEMENT	HOT-MIX ASPHALT SHOULDERS, 6"	AGGREGATE SHOULDERS, TYPE A
		(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)
STAGE 4						
MINKLER RD						
54+37	61+93	LT		782	782	85
STAGE 4A						
ORCHARD RD						
798+20.85		LT		474		
798+20.85		RT		527		
63+70	65+00	MEDIAN		87	87	
65+00	70+33	MEDIAN		740	740	
STAGE 4B						
801+50		LT		59		
STAGE 4C						
ORCHARD RD						
798+20.85		RT		996		
795+00		RT		44		
STAGE 5						
ORCHARD RD						
798+20.85		RT		496		
NOT STAGED						
BUELL RD						
788+57.11				98		
DOUGLAS ST						
837+87.36				104		
PARADISE PKW						
842+85.83				274		
HERRENS LN						
793+05.40				94		
CALUMET ST						
883+89.28				37		
MUNICIPAL RD						
895+84.12				158		
FRANKLIN ST						
897+30.00				69		
BELL CT						
901+20.00				216		
BUDLONG RD						
88+75.84				40		
CONTINGENCY						
	10%			482		
TOTALS			5,304	37,060	37,060	166
						1,688

COST FOR REMOVING QUANTITY OF TEMPORARY RAMP WILL BE INCIDENTAL TO TEMPORARY PAVEMENT REMOVAL OR PAVEMENT REMOVAL. NO ADDITIONAL PAYMENT WILL BE ALLOWED.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: NONE
DATE 7/3/2012

DRAWN BY
CHECKED BY RG