

F.A.P. STATE	SECTION	COUNTY	TOTAL SHEETS
311	0-1 R	KENDALL	514
STA.	TO STA.		71
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT	

SCHEDULE OF QUANTITIES

LOCATION	TEMPORARY PAVEMENT MARKING, LINE 4"					TEMPORARY PAVEMENT MARKING, LINE 24"	TEMPORARY PAVEMENT MARKING, LETTERS AND SYMBOLS			WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
	SOLID WHITE (FOOT)	SKIP-DASH WHITE (FOOT)	DOTTED WHITE (FOOT)	SOLID YELLOW (FOOT)	DOUBLE YELLOW (FOOT)	SOLID WHITE (FOOT)	LEFT ARROW (SQ FT)	RIGHT ARROW (SQ FT)	RIGHT AND THROUGH ARROW (SQ FT)	TEMP. (SQ FT)	EXIST. (SQ FT)	(EACH)
	STAGE 4											
IL RTE 71												
STA. 774+45 TO STA. 787+00	2500	0	0	0	2500	0	0	0	0	1667	1075	33
STA. 787+00 TO STA. 801+00	3257	0	76	0	2212	44	46.8	0	76	2058	881	71
STA. 801+00 TO STA. 816+00	3100	0	76	0	3000	0	15.6	0	26	2102	667	10
STAGE 4 SUBTOTALS	12,659	0	152	0	11,530	66	62.4	0.0	104.0	8,028	4,246	181
STAGE 4A												
IL RTE 71												
STA. 787+00 TO STA. 801+00	717	0	0	0	0	0	0	0	0	240	0	0
ORCHARD ROAD / MINKLER ROAD												
STA. 53+70 TO STA. 62+59.67	1554	0	0	0	1551	11	0	0	0	890	0	0
STA. 62+59.67 TO STA. 74+78	1784	0	0	0	2223	11	0	0	0	1315	0	0
STAGE 4A SUBTOTALS	4,055	0	0	0	3,774	22	0.0	0.0	0.0	2,445	0	0
STAGE 4B												
IL RTE 71												
STA. 787+00 TO STA. 801+00	973	0	0	0	0	0	0	0	0	325	0	0
STA. 801+00 TO STA. 816+00	104	0	26	0	0	0	0	0	0	44	0	0
ORCHARD ROAD / MINKLER ROAD												
STA. 62+59.67 TO STA. 74+78	200	0	0	0	0	0	0	0	0	67	0	0
STAGE 4B SUBTOTALS	1,277	0	26	0	0	0	0.0	0.0	0.0	436	0	0
STAGE 4C												
IL RTE 71												
STA. 787+00 TO STA. 801+00	1747	0	0	0	0	0	0	0	0	584	0	0
ORCHARD ROAD / MINKLER ROAD												
STA. 53+70 TO STA. 62+59.67	1678	0	0	0	1572	11	0	0	0	664	0	0
STA. 62+59.67 TO STA. 74+78	2245	0	0	0	2245	11	0	0	0	1312	0	0
STAGE 4C SUBTOTALS	5,670	0	0	0	3,817	22	0.0	0.0	0.0	2,560	0	0
STAGE 5												
IL RTE 71												
STA. 774+00 TO STA. 787+00	2813	0	0	0	2613	0	0	0	0	1734	0	0
STA. 787+00 TO STA. 801+00	3351	0	76	0	2180	44	46.8	15.6	52	2075	0	0
STA. 801+00 TO STA. 816+00	3724	0	125	0	3000	0	46.8	15.6	0	2348	0	0
ORCHARD ROAD / MINKLER ROAD												
STA. 53+70 TO STA. 62+59.67	964	0	0	0	964	11	0	0	0	665	0	0
STA. 62+59.67 TO STA. 74+78	1940	0	0	0	1940	11	0	0	0	1316	0	0
STAGE 5 SUBTOTALS	12,592	0	201	0	10,697	66	93.6	31.2	52.0	8,138	0	0
STAGE 5A												
IL RTE 71												
STA. 787+00 TO STA. 801+00	861	0	0	0	0	0	0	0	0	287	0	0
ORCHARD ROAD / MINKLER ROAD												
STA. 53+70 TO STA. 74+78	3426	0	0	0	898	22	0	0	0	121	0	0
STAGE 5A SUBTOTALS	4,287	0	0	0	698	22	0.0	0.0	0.0	408	0	0

SUBSTITUTE TAPE FOR PAINT ON NEW CONCRETE SURFACES AS DIRECTED BY THE ENGINEER. AN ESTIMATED QUANTITY HAS BEEN INCLUDED IN THE SUMMARY OF QUANTITIES FOR TYPE III TAPE.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: NONE
DATE: 7/3/2012
DRAWN BY:
CHECKED BY: RG

IE PROJ: 085926
PLOT DATE: 7/3/2012
FILE NAME: G:\085926\010\11\SCHED_06.SHT