

PERMANENT PAVEMENT MARKING SCHEDULE (1 OF 2)

LOCATION	MODIFIED URETHANE PAVEMENT MARKING - LETTERS & SYMBOLS												RAISED REFLECTIVE PAVEMENT MARKER						TWO-WAY CRYSTAL WITH RED MARKER	TWO-WAY AMBER WITH RED MARKER	
	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"												ONE - WAY CRYSTAL		ONE - WAY AMBER		TWO-WAY AMBER				
	WHITE	WHITE	YELLOW	DBL YELLOW	YELLOW SKIP	WHITE SKIP	WHITE	WHITE DOTTED	WHITE	YELLOW	WHITE	WHITE	EACH	EACH	EACH	EACH	EACH	EACH			
SO FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT			
US ROUTE 34																					
515+00	TO	519+00		800.2		400.0								7	13			8			
519+00	TO	534+00	344.8	3213.4	2137.0	1120.7		510.0	860.0	880.0		170.0	42.6	25	28	30	21				
534+00	TO	549+00		3000.0	3000.0			760.0						38							
549+00	TO	564+00	261.8	3130.6	2858.3	173.3		700.0	865.0	880.0			48.0	35	24						
564+00	TO	579+00		3000.0	3000.0			750.0						37							
579+00	TO	594+00		2088.7	3000.0			750.0		911.4				37							
594+00	TO	609+00		2401.3	3000.0			750.0	360.0	238.5				38	10						
609+00	TO	624+00		3000.0	3000.0			750.0						37							
624+00	TO	639+00		1490.0	3000.0			750.0	360.0	1150.0				38	10						
639+00	TO	654+00		3000.0	3000.0			750.0						38							
654+00	TO	669+00		3000.0	3000.0			750.0						37							
669+00	TO	684+00		3000.0	3000.0			750.0						37							
684+00	TO	699+00	261.8	3121.4	2875.3	158.0		680.0	860.0	880.0			55.4	35	24						
699+00	TO	714+00		3000.0	3000.0			750.0						37							
714+00	TO	729+00	324.2	3170.8	2866.6	189.6		680.0	1140.0	1140.0			40.8	34	32						
729+00	TO	744+00		3000.0	3000.0			750.0						37							
744+00	TO	756+00	168.2	2400.0	2276.1	42.0		600.0	430.0	440.0				29	12						
756+00	TO	768+00		2400.0	2400.0			600.0						22							
768+00	TO	783+00	261.8	3170.8	2866.6	189.6		670.0	860.0	880.0			40.8	35	24						
783+00	TO	798+00		3000.0	3000.0			760.0						37							
798+00	TO	813+00	298.0	3064.5	2872.8	101.6		640.0	645.0	660.0			26.9	32	21	8	7				
813+00	TO	825+00		2404.4	683.1	1070.1		110.0				95.2		6	27	21	22	15			
IL 94 / 116																					
10+00	TO	18+00		1600.2		1441.0						341.3	41.0				32	2			
18+00	TO	33+00	93.6	2303.9	1902.2	781.8		530.0	530.0			319.4			14		75				
33+00	TO	48+15		2068.7	781.2	703.4							58.6				20	8			
RAMP A																					
0+00	TO	10+00		1000.0	343.7			360.5		279.7					9	41	9				
10+00	TO	21+98.13		1250.0	1175.3			409.1		89.6			40.0				5	13			
RAMP B																					
0+00	TO	13+00		1337.0	1021.4			119.2													
13+00	TO	24+31.78		1132.8				283.9													
RAMP C																					
0+00	TO	10+50		1051.0	394.6			361.8		274.8					9	41	10				
10+50	TO	22+21.40		1219.6	1140.7			409.1		79.2			40.0				4	14			
RAMP D																					
0+00	TO	13+00		1340.8	1188.0			102.9													
13+00	TO	24+48.52		1149.5				300.7													
SUBTOTAL 1			2,014	75,310	65,783	6,371	0	14,210	9,257	8,590	723	926	434	701	251	154	205	15	30	27	27