

SUMMARY OF QUANTITIES

LOCATION OF WORK: MCLEAN CO.
 FAP 315 (US 136)
 RURAL TWO LANE
 FUNDING BREAKOUT: 80 % FED / 20 % STATE
 CONSTRUCTION TYPE CODE: 0005

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
44022051	PARTIAL DEPTH REMOVAL 8 1/2"	SQ YD	682.0
44200934	CLASS B PATCH, TYPE II, 8 INCH	SQ YD	450.0
44200942	CLASS B PATCH, TYPE III, 8 INCH	SQ YD	243.0
44200944	CLASS B PATCH, TYPE IV, 8 INCH	SQ YD	94.0
44201299	DOWEL BARS 1 1/2"	EACH	1,642.0
44213200	SAW CUTS	FOOT	3,751.0
44213208	TIE BARS 1 1/4"	EACH	60.0
48101200	AGGREGATE SHOULDER, TYPE B	TON	834.0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	129.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	968.0
54248510	CONCRETE COLLAR	CU YD	0.5
55100400	STORM SEWER REMOVAL 10"	FOOT	36.0
60255500	MANHOLES TO BE ADJUSTED	EACH	1.0
60624610	CORRUGATED MEDIAN (DOWELLED)	SQ. FT.	526.0

SUMMARY OF QUANTITIES

LOCATION OF WORK: MCLEAN CO.
 FAP 315 (US 136)
 RURAL TWO LANE
 FUNDING BREAKOUT: 80 % FED / 20 % STATE
 CONSTRUCTION TYPE CODE: 0005

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
61101011	STORM SEWERS PROTECTED, CLASS A, 10"	FOOT	36.0
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	2,050.0
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	175.0
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	21.0
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) FLARED	EACH	1.0
63200310	GUARDRAIL REMOVAL	FOOT	3,252.0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4.0
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1.0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0

* SPECIALTY ITEM

FILE NAME: c:\pwworkh\pwworkh\egleby\d0244982\05707	USER NAME: egleby	DESIGNED: -	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.:	SECTION:	COUNTY:	TOTAL SHEETS:	SHEET NO.:
315	119RS-4, 1BRS & 157-101RS	MCLEAN	225					6				
PLOT SCALE: 1/8" = 1'-0"	CHECKED: -	REVISED: -	REVISED: -		SCALE:	SHEET NO. OF SHEETS:	STA. TO STA.:	CONTRACT NO. 70783				
PLOT DATE: 10/19/2012	DATE: -	REVISED: -	REVISED: -					ILLINOIS FED. AID PROJECT				