

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-13	CHRISTIAN	437	32
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

GUARDRAIL SCHEDULE

STATION TO STATION	SIDE	TRAFFIC BARRIER TERMINAL					AGGREGATE SHOULDERS TYPE B (SPECIAL) TON
		63000001	63100085	63100087	63100167	63100169	
		SPBGR TYPE A (6 FOOT POSTS) FOOT	TYPE 6	TYPE 6A	TYPE 1 SPECIAL (TANGENT)	TYPE 1 SPECIAL (FLARED)	
FAP 322 (US 51)							
467+47.52	469+77.14	RT OS	134.38	1			50.0
467+61.52	469+66.20	RT IS	109.38	1			43.3
470+61.27	473+78.68	LT OS	221.88	1			77.7
470+76.50	474+56.23	LT IS	284.38	1		1	87.3
470+83.78	473+76.31	RT IS	196.88	1		1	68.8
470+94.72	472+74.75	RT OS	84.38	1		1	44.1
TR 255							
40+26.48	41+87.42	RT	59.38		1	1	40.8
40+87.76	42+03.58	LT	21.88		1	1	30.1
43+36.42	44+53.68	RT	21.88		1	1	30.5
43+52.58	45+22.00	LT	71.88		1	1	42.9
TOTALS			1206.30	6	4	8	515.4
USE			1206.30	6	4	8	516

* GUARDRAIL PLACED AT 1:15 TAPER.

MARKER SCHEDULE

STATION TO STATION	SIDE	MARKERS		
		78200410	78200520	78201000
		GUARDRAIL MARKERS TYPE A	BARRIER WALL MARKERS TYPE B	TERMINAL MARKER DIRECT APPLIED
FAP 322 (US 51)				
467+47.52	472+74.75	NBL OUT	5	2
467+61.52	473+76.31	NBL IN	7	2
470+61.27	473+78.68	SBL OUT	4	2
470+76.50	474+56.23	SBL IN	5	2
TR 255				
40+26.48	44+53.68	RT	5	2
40+87.76	45+22.00	LT	5	2
TOTAL			31	10

CONCRETE PAD

STATION	SIDE	WIDTH	LENGTH	SQ YD
FAP 322 (US 51)				
436+19.8	RT	8.0	39.9	35.5
436+20.4	LT	8.0	42.3	37.6
TOTAL				73.1
USE				74

PAVEMENT PATCHING, TYPE II, 12 INCH

STATION	SIDE	LENGTH	WIDTH	SQ YD
EX US 51				
1233+85.00	LT	4.75	13.25	7.0
1233+85.00	RT	4.75	13.25	7.0
EX TR 257				
21+51.0	LT & RT	6.50	14.00	10.1
TOTALS				24.1
USE				25

WOVEN WIRE FENCE, 4'

STATION TO STATION	SIDE	FOOT
FAP 322 (US 51)		
539+65.0	546+85.0	LT
547+35.0	549+35.0	LT
TOTAL		921.1
USE		922

TEMPORARY CONCRETE BARRIER

STATION TO STATION	SIDE	SECTIONS	FOOT
US 51 RELOCATION - STAGE 1A			
104+06.3	107+08.0	LT	24
US 51 RELOCATION - STAGE 1B			
102+45.5	109+83.4	LT	35
TOTAL			747.3

RELOCATE TEMPORARY CONCRETE BARRIER

STATION TO STATION	SIDE	SECTIONS	FOOT
US 51 RELOCATION - STAGE 1B			
102+45.5	109+83.4	LT	24
TOTAL			304.0

PERMANENT BARRICADES

STATION	SIDE	EACH
FAP 322 (US 51)		
336+75	LT	2
TOTAL		2

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3

STATION	SIDE	EACH
US 51 RELOCATION		
104+06.3	LT	1
107+08.0	LT	1
TOTAL		2

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE) TEST LEVEL 3

STATION	SIDE	EACH
US 51 RELOCATION		
102+45.5	LT	1
109+83.4	LT	1
TOTAL		2

REVISIONS	
NAME	DATE
SEB	10/10/12

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 SHEET 8 OF 22
 FAP 322 (US 51)
 SECTION 11-13
 CHRISTIAN COUNTY

SCALE: DATE 4/11 DRAWN BY EBB CHECKED BY