

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-13	CHRISTIAN	437	36
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PIPE UNDERDRAIN SCHEDULE  
60107600 60108100 60100060 78001120

NORTHBOUND INSIDE EDGE OF PAVEMENT							
PIPE UNDERDRAIN 4"			PIPE UNDERDRAIN 4" (SPECIAL)			CONCRETE HEADWALL EACH	PAINT PAVEMENT MARKING 5" FOOT
BEGINNING STATION	ENDING STATION	LENGTH FOOT	OUTLET STATION	LENGTH FOOT	CONNECT TO STRUCTURE		
FAP 322 (US 51)							
340+50	345+50	500.0	340+50	16.0		1	2.0
345+50	350+20	470.0	345+50	18.0		1	2.0
350+20	352+00	180.0	352+00	22.5	Y		
352+00	357+00	500.0	357+00	16.0	Y		
357+00	360+30	330.0	357+00		Y		
372+46	375+00	254.0	375+00	22.0	Y		
375+00	380+85	585.0	375+00		Y		
382+65	386+00	335.0	386+00	16.5		1	2.0
386+00	390+00	400.0	390+00	23.0	Y		
390+00	393+50	350.0	390+00		Y		
393+50	397+00	350.0	393+50	18.5		1	2.0
397+00	400+50	350.0	397+00	18.5		1	2.0
400+50	404+50	427.5	404+50	18.8		1	2.0
404+50	408+54	404.0	408+54	23.0	Y		
408+54	414+13	559.0	408+54		Y		
415+93	420+00	407.0	415+93	18.5	Y		
420+00	424+72	472.0	420+00	15.8		1	2.0
424+72	429+00	428.0	429+00	16.8		1	2.0
429+00	433+00	400.0	433+00	16.8		1	2.0
433+00	436+98	398.0	436+98		Y		
436+98	441+00	402.0	436+98		Y		
441+00	445+00	400.0	441+00	16.8		1	2.0
445+00	450+20	520.0	445+00	19.4		1	2.0
452+00	456+50	450.0	456+50	16.8		1	2.0
456+50	461+00	450.0	461+00	13.7		1	2.0
461+00	466+09	509.0	466+09		Y		
468+10	469+33	123.0	469+33	16.3		1	2.0
471+18	473+30	212.0	473+30		Y		
473+30	478+00	470.0	473+30		Y		
478+00	483+00	500.0	478+00	16.8		1	2.0
483+00	488+00	500.0	483+00	16.8		1	2.0
488+00	492+63	463.0	488+00	16.8		1	2.0
492+63	496+52	389.0	496+52	14.5	Y		
498+52	502+50	398.0	502+50	15.8		1	2.0
502+50	507+00	450.0	507+00	18.1		1	2.0
507+00	511+36	436.0	511+36		Y		
511+36	516+00	464.0	511+36		Y		
516+00	520+80	480.0	516+00	13.6		1	2.0
522+61	525+19	258.0	522+61		Y		
525+19	530+00	481.0	530+00	19.4		1	2.0
530+00	534+50	450.0	534+50	16.8		1	2.0
534+50	539+00	450.0	539+00		Y		
539+00	542+50	350.0	542+50	11.8		1	2.0
542+50	546+10	360.0	546+10		Y		
548+10	552+00	390.0	552+00	16.3		1	2.0
552+00	555+00	300.0	555+00	18.1		1	2.0
SUBTOTALS		18754.5		558.5		25	50.0

PIPE UNDERDRAIN SCHEDULE  
60107600 60108100 60100060 78001120

NORTHBOUND OUTSIDE EDGE OF PAVEMENT							
PIPE UNDERDRAIN 4"			PIPE UNDERDRAIN 4" (SPECIAL)			CONCRETE HEADWALL EACH	PAINT PAVEMENT MARKING 5" FOOT
BEGINNING STATION	ENDING STATION	LENGTH FOOT	OUTLET STATION	LENGTH FOOT	CONNECT TO STRUCTURE		
FAP 322 (US 51)							
340+50	343+38	288.0	340+50	19.8		1	2.0
358+60	359+85	125.0	358+60	16.5		1	2.0
362+15	367+00	485.0	362+30	26.2		1	2.0
367+00	372+00	500.0	372+00	28.9		1	2.0
372+00	375+00	300.0	375+00	24.9		2	2.0
375+00	378+50	350.0	375+00				
378+50	382+00	350.0	378+50	21.3		1	2.0
382+00	386+00	400.0	386+00	21.3		1	2.0
386+00	390+00	400.0	390+00	22.8		2	2.0
390+00	393+50	350.0	390+00				
393+50	397+00	350.0	393+50	19.8		1	2.0
397+00	400+50	350.0	397+00	21.3		1	2.0
400+50	404+50	427.5	404+50	21.2		1	2.0
404+50	408+54	404.0	408+54	22.2		2	2.0
408+54	411+00	246.0	408+54				
411+00	414+05	305.0	411+00	14.6		1	2.0
416+07	420+00	393.0	416+07	19.8		1	2.0
420+00	424+72	472.0	420+00	19.8		1	2.0
424+72	429+00	428.0	429+00	19.8		1	2.0
429+00	433+00	400.0	433+00	19.8		1	2.0
433+00	436+98	398.0	436+98		Y		
436+98	441+00	402.0	436+98		Y		
441+00	445+00	400.0	441+00	19.8		1	2.0
445+00	449+09	409.0	445+00	22.2		1	2.0
449+09	450+25	116.0	450+25	21.7		1	2.0
451+75	456+50	475.0	456+50	19.8		1	2.0
456+50	461+00	450.0	461+00	17.4		1	2.0
461+00	466+09	509.0	466+09		Y		
468+21	469+41	120.0	469+41	23.2		1	2.0
471+28	473+30	202.0	473+30		Y		
473+30	478+00	470.0	473+30		Y		
478+00	483+00	500.0	478+00	19.8		1	2.0
483+00	488+00	500.0	483+00	19.8		1	2.0
488+00	492+63	463.0	488+00	19.8		1	2.0
492+63	498+00	537.0	498+00	19.8		1	2.0
498+00	502+50	450.0	502+50	19.8		1	2.0
502+50	507+00	450.0	507+00	19.8		1	2.0
507+00	511+36	436.0	511+36		Y		
511+36	516+00	464.0	511+36		Y		
516+00	520+72	472.0	516+00	15.9		1	2.0
522+61	525+19	258.0	522+61		Y		
525+19	530+00	481.0	530+00	25.7		1	2.0
530+00	534+50	450.0	534+50	19.8		1	2.0
534+50	539+00	450.0	539+00		Y		
539+00	542+50	350.0	542+50	19.8		1	2.0
542+50	546+10	360.0	546+10		Y		
546+10	551+00	490.0	551+00	19.8		1	2.0
551+00	555+00	400.0	555+00	19.8		1	2.0
SUBTOTALS		18785.5		723.7		38	70.0
TOTALS		79244.0		2755.8		138	258.0
USE		79244		2756		138	258

REMOVE AND REPLACE CONCRETE HEADWALLS FOR PIPE UNDERDRAINS

X6015015		
STATION	SIDE	EACH
FAP 322 (US 51)		
567+63	LT	1
567+63	RT	1
570+50	LT	1
570+50	RT	1
TOTAL		4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF QUANTITIES  
SHEET 12 OF 22  
FAP 322 (US 51)  
SECTION 11-13  
CHRISTIAN COUNTY

SCALE: DATE 8/12 DRAWN BY EBB CHECKED BY