

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-13	CHRISTIAN	437	44
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STRIPING SCHEDULE

STATION TO STATION	LANE	SIDE	DESCRIPTION	78009005 78009005 78009006 78009012				X7830072 X7830074		78003120 78003130		78003100 78004220		78004230 78004240		78004250 78004280		78004200 78001120 78001120 78100100		
				MODIFIED URETHANE PAVEMENT MARKINGS		GROOVING FOR RECESSED PAVEMENT MARKING		PREFORMED PLASTIC PAVEMENT MARKINGS - TYPE B								PAINT PVTM MARKINGS		RAISED PAVEMENT MARKERS		
				LINE 5" YELLOW	LINE 5" WHITE	LINE 6" WHITE	LINE 12" YELLOW	6"	7"	STANDARD LINE 5" WHITE	STANDARD LINE 6" WHITE	STANDARD L & S WHITE	INLAID LINE 5" WHITE	INLAID LINE 6" WHITE	INLAID LINE 8" WHITE	INLAID LINE 12" WHITE	INLAID LINE 24" WHITE	INLAID L & S WHITE	LINE 5" YELLOW	LINE 5" WHITE
			FOOT			SO FT		FOOT			SO FT				EA					
FAP 322 (US 51)			463+00.0	478+00.0	NBL	LT	EDGE LINE/TURN LANE	1430.4	1430.4					341	139.6	37.4	75			10
			CL	SKIP-DASH					50.0		50.0			330						19
			RT	EDGE LINE/TURN LANE			1299.1	1299.1					321	132.3	67.6		62.4			9
		SBL	LT	EDGE LINE/TURN LANE			1294.7	1294.7	184.0		184.0	31.2		225	132.3	67.6		31.2		10
			CL	SKIP-DASH						50.0				330						19
			RT	EDGE LINE/TURN LANE	1430.6		1430.6	1430.6	174.5		174.5	31.2		238.5	139.6	37.4		43.8		10
478+00.0	493+00.0	NBL	LT	EDGE LINE/TURN LANE	1500.0		1500.0	1500.0						380						19
			CL	SKIP-DASH										380						19
		SBL	LT	EDGE LINE			1500.0	1500.0												
			CL	SKIP-DASH										380						19
			RT	EDGE LINE	1500.0		1500.0	1500.0												
493+00.0	508+00.0	NBL	LT	EDGE LINE/TURN LANE	1430.5		1430.5	1430.5						446.9						
			CL	SKIP-DASH										380						19
			RT	EDGE LINE			1500.0	1500.0												
		SBL	LT	EDGE LINE			1500.0	1500.0												
			CL	SKIP-DASH										380						19
			RT	EDGE LINE/TURN LANE	1430.5		1430.5	1430.5					689.7							
508+00.0	523+00.0	NBL	LT	EDGE LINE/TURN LANE	1430.9		1430.9	1430.9					413	143.1	38.4		75			10
			CL	SKIP-DASH										380						19
			RT	EDGE LINE/TURN LANE			1276.3	1276.3						389	129.7	65.6		62.4		9
		SBL	LT	EDGE LINE/TURN LANE			1299.2	1299.2						81.1	129.7	65.6		15.6		3
			CL	SKIP-DASH										380						19
			RT	EDGE LINE/TURN LANE	1430.7		1430.7	1430.7					88	143.1	38.4		28.2			3
523+00.0	538+00.0	NBL	LT	EDGE LINE	1500.0		1500.0	1500.0						380						19
			CL	SKIP-DASH										380						19
			RT	EDGE LINE			1500.0	1500.0												
		SBL	LT	EDGE LINE/TURN LANE			1500.0	1500.0									46.8			6
			CL	SKIP-DASH										380						19
			RT	EDGE LINE/TURN LANE	1500.0		1500.0	1500.0					325				46.8			7
538+00.0	553+00.0	NBL	LT	EDGE LINE/TURN LANE	1430.6		1430.6	1430.6						448			62.4			9
			CL	SKIP-DASH										380						19
			RT	EDGE LINE			1500.0	1500.0												
		SBL	LT	EDGE LINE			1362.0	1362.0												
			CL	SKIP-DASH										380						19
			RT	EDGE LINE/TURN LANE	1430.8		1430.8	1430.8					584.6							
553+00.0	568+00.0	NBL	LT	EDGE LINE	1463.0		1463.0	1463.0						370						18
			CL	SKIP-DASH										370						18
			RT	EDGE LINE			1463.0	1463.0												
		SBL	LT	EDGE LINE			1500.0	1500.0												
			CL	SKIP-DASH										380						19
			RT	EDGE LINE/TURN LANE	1500.0		1500.0	1500.0					105							
568+00.0	583+00.0	SBL	LT	EDGE LINE/TURN LANE			590.0	590.0	283.0		283.0									
			CL	SKIP-DASH										150						29
			RT	EDGE LINE	590.0		590.0	590.0												

11/7/2012 G:\Files\010351\South Plains New VADD Sheets\06\2861-ant-Schedule.dgn

REVISIONS	
NAME	DATE
SEB	10/10/12
SEB	11/7/12

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
SHEET 20 OF 22
FAP 322 (US 51)
SECTION 11-13
CHRISTIAN COUNTY

SCALE: _____ DRAWN BY: EBB
DATE: _____ CHECKED BY: _____