

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY	STRUCTURAL		
51500100	NAME PLATES	EACH	1		1		
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2		2		
54011208	PRECAST CONCRETE BOX CULVERTS 12' X 8'	FOOT	240		240		
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	125	125			
54213453	END SECTIONS 18"	EACH	2	2			
60240305	INLETS, TYPE B, TYPE 10 FRAME AND GRATE	EACH	1	1			
60262700	INLETS TO BE RECONSTRUCTED	EACH	1	1			
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	1	1			
60500060	REMOVING INLETS	EACH	1	1			
60602800	CONCRETE GUTTER, TYPE B	FOOT	173	173			
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	200	200			
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	37.5	37.5			
63200310	GUARDRAIL REMOVAL	FOOT	138	138			
63500105	DELINEATORS	EACH	4	4			

* SPECIALTY ITEM



USER NAME - Plotted by Roadways?
 DESIGNED - SGL
 DRAWN - SGL
 CHECKED - FML
 DATE - 9/2012
 PLOT SCALE - 1/8" = 1'-0"
 PLOT DATE - 10/19/2012

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

IL ROUTE 96 OVER INLET DITCH
 SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 04 OF 06 SHEETS STA. TO STA.

F.A.P. RTE. 510	SECTION 1208-3	COUNTY HANCOCK	TOTAL SHEETS 38	SHEET NO. 6
CONTRACT NO. 72B67				
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				