

STRIPING ITEMS-US 67

LOCATION	PAVEMENT MARKING LINE 6'' DOTTED (WHITE) (FOOT)	PAVEMENT MARKING LINE 6'' SOLID (WHITE) (FOOT)	PAVEMENT MARKING LINE 8'' SOLID (WHITE) (FOOT)	PAVEMENT MARKING LINE 8'' SOLID (YELLOW) (FOOT)	PAVEMENT MARKING LINE 12'' SOLID (WHITE) (FOOT)	PAVEMENT MARKING LINE 12'' SOLID (YELLOW) (FOOT)	PAVEMENT MARKING LETTERS & SYMBOLS "YIELD" (SOFT)	PAVEMENT MARKING LETTERS & SYMBOLS ARROWS (SOFT)
MORGAN COUNTY								
US 67 & FAS 310/IL RTE 967, MURRAYVILLE/CUNNINGHAM RD (NBL)	24.05	60.89	112.26		52.97			
US 67 & FAS 310/IL RTE 967, MURRAYVILLE/CUNNINGHAM R (SBL)	32.73	5.87	165.53		87.07		12.60	
US 67 & TR 303/ANDRAS RD (NBL)	23.33	20.65	166.92		67.27		12.60	15.60
US 67 & TR 303/ANDRAS RD (SBL)	23.33	68.16	163.49		56.96		12.60	15.60
US 67 & TR 299/BIRDSELL RD & FAS 617 (NBL)	23.19	14.36	222.90		87.45		12.60	15.60
US 67 & TR 299/BIRDSELL RD & FAS 617 (SBL)	41.07	23.62	178.61		74.68		12.60	15.60
US 67 & TR 110/THADY RD (NBL)	23.44	19.13	166.79		60.32		12.60	15.60
US 67 & TR 110/THADY RD (SBL)	23.43	45.58	160.68		59.99		12.60	15.60
US 67 & TR 315/MIDWAY RD (NBL)	22.63	19.28	178.88		72.61		12.60	31.20
US 67 & TR 315/MIDWAY RD (SBL)	22.60	67.76	169.12		59.07		12.60	31.20
US 67 & FAS 609/ WOODSON WINCHESTER RD/CH 28 (NBL)	41.36	32.24	234.90		94.61		12.60	31.20
US 67 & FAS 609/ WOODSON WINCHESTER RD/CH 28 (SBL)	41.35	42.79	227.68		87.47		12.60	31.20
US 67 & CH 23/LYNNVILLE WOODSON RD & TR 259 (NBL)	41.44	15.99	233.96		94.26		12.60	15.60
US 67 & CH 23/LYNNVILLE WOODSON RD & TR 259 (SBL)	41.44	30.87	229.17		86.34		12.60	15.60
US 67 & TR 223/OLD AIRPORT RD (NBL)	23.46	24.64	167.97		66.08		12.60	15.60
US 67 & TR 223/OLD AIRPORT RD (SBL)	23.46	29.65	162.41		64.22		12.60	15.60
US 67 & S15.70/OLD US 67 (NBL)	44.73	30.55	121.83		53.88			
US 67 & S15.70/OLD US 67 (SBL)	22.50	5.78	168.87		95.58		12.60	
US 67 & TR 78/MARKHAM RD (EBL)	28.82	39.89	269.51		115.89		12.60	
US 67 & TR 78/MARKHAM RD (WBL)	28.82	39.89	269.51		124.64		12.60	
US 67 & TR 56/THOMASON ROAD (EBL)	25.78	45.49	197.71		83.29		12.60	
US 67 & TR 56/THOMASON ROAD (WBL)	27.16	46.35	249.72		116.15		12.60	
US 67 & S13.44/CHAPIN CEMETERY ROAD (EBL)	24.76	14.57	143.09		68.88		12.60	
US 67 & S13.44/CHAPIN CEMETERY ROAD (WBL)	44.05	30.98	80.52		40.30			
SCOTT COUNTY								
US 67 & MUN 1100/FIELD RD & S1.48/MAIN ST (NBL)	22.89	39.62	241.46		109.17		12.60	
US 67 & MUN 1100/FIELD RD & S1.48/MAIN ST (SBL)	22.24	34.14	231.45		94.92		12.60	
US 67 & MUN 1040/5TH ST (NBL)	23.49	29.29	162.68		59.34			
US 67 & MUN 1040/5TH ST (SBL)	40.74	6.17	143.28		64.66		12.60	15.60
US 67 & FAS 608 & 1.48/MAIN ST (NBL)	41.67	30.40	185.21		69.27		12.60	15.60
US 67 & FAS 608 & 1.48/MAIN ST (SBL)	23.75	14.05	220.76		94.35		12.60	15.60
US 67 & TR 166/HORSE FARM RD (NBL)	30.20	32.70	174.79		63.84		12.60	15.60
US 67 & TR 166/HORSE FARM RD (SBL)	29.21	33.04	175.23		67.05		12.60	15.60
US 67 & TR 137/STEVENSON RD (NBL)	19.47	5.93	157.37		79.95		12.60	15.60
US 67 & TR 137/STEVENSON RD (SBL)	11.51	27.82	54.11		26.02			
TOTAL	984.1	1,028.1	6,188.4		2,598.6		365.4	374.4

FILE NAME =	USER NAME = sparksgw	DESIGNED - EK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\sparksgw\0290765\06721-sht-schedule.dgn	DRAWN - EK	REVISED -											
Default	PLOT SCALE = 100.0000' / in.	CHECKED - JM	REVISED -		SCALE: NTS	SHEET	OF	SHEETS	STA.	TO	STA.	ILLINOIS FED. AID PROJECT	
	PLOT DATE = Oct-17-2012 01:57:09PM	DATE -	REVISED -									CONTRACT NO. 72F21	