

PAVEMENT SCHEDULE

LOCATION STATION TO STATION FAP 662/67 (IL 4/97)	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	PCC SURF REM. BUTT-JOINT (SQ YD)	HOT-MIX ASPHALT SURF. REM. BUTT-JOINT (SQ YD)	HMA SURF. REM. VARI. DEPTH (SQ YD)	HMA LEVEL BINDER (MM) N90 (TON)	HMA LEVEL BINDER (MM) N50 (TON)	POLY HMA SURF. COURSE MIX "E", N90 (1 1/2") (TON)	POLY HMA SURF. COURSE MIX "C", N50 (1 1/2") (TON)	BIT. MAT. PRIME CT. (TON)	AGG. PRIME CT. (TON)
IL 97 (JEFFERSON ST.)												
STA. 89+55.20 TO STA. 94+33.75	478.55	22 TO 36	1542.0			1,542.0	64.8		129.5		0.59	3.08
STA. 94+33.75 TO STA. 97+61.07	327.32	36 TO 38	1345.6			1,345.6	56.5		113.0		0.51	2.69
STA. 97+61.07 TO STA. 99+00.00	138.93	38	586.6			586.6	24.6		49.3		0.22	1.17
STA. 99+00.00 TO STA. 101+13.04	213.04	51 TO 50	1195.4			1,195.4	50.2		100.4		0.45	2.39
STA. 101+15.43 TO STA. 102+87.74	172.31	50 TO 40	861.5			861.5	36.2		72.4		0.33	1.72
STA. 102+87.74 TO STA. 102+97.74	10.00	40	44.4		44.4		1.9		3.7		0.02	0.09
STA. 102+97.74 TO STA. 103+33.45	35.71	40 TO 39	156.7				6.6		13.2		0.06	0.31
STA. 103+33.45 TO STA. 104+12.85	79.40	39	344.1				14.5		28.9		0.13	0.69
STA. 104+12.85 TO STA. 104+99.63	86.78	39 TO 44	400.2				16.8		33.6		0.15	0.80
STA. EQ. 104+99.63 BK = 107+95.18 AH												
STA. 107+95.18 TO STA. 110+30.77	235.59	44.00 TO 60	1361.2				57.2		114.3		0.52	2.72
IL 97 (JEFFERSON ST.)												
RIGHT												
STA. 110+30.77 TO STA. 112+13.38	182.61	29.00 TO 26	558.0				23.4		46.9		0.21	1.12
STA. 112+13.38 TO STA. 112+62.61	49.23	26	142.2				6.0		11.9		0.05	0.28
STA. 112+62.61 TO STA. 114+05.17	142.56	26.00 TO 36	491.0				20.6		41.2		0.19	0.98
STA. 114+05.17 TO STA. 115+89.58	184.41	36	737.6				31.0		62.0		0.28	1.48
STA. 115+89.58 TO STA. 120+45.53	455.95	24	1215.9				51.1		102.1		0.46	2.43
STA. 115+81.23 TO STA. 116+91.84	110.61	1.00 TO 12	79.9				3.4		6.7		0.03	0.16
STA. 116+91.84 TO STA. 119+14.11	222.27	12	296.4				12.4		24.9		0.11	0.59
STA. 119+14.11 TO STA. 120+42.49	128.38	VARIES	383.2				16.1		32.2		0.15	0.77
STA. 116+83.73 TO STA. 117+00.00	16.27	0.00 TO 12	10.8				0.5		0.9		0.00	0.02
STA. 117+00.00 TO STA. 120+51.17	351.17	12	468.2				19.7		39.3		0.18	0.94
STA. 121+44.92 TO STA. 121+93.71	48.79	31.00 TO 25	151.8				6.4		12.8		0.06	0.30
STA. 121+93.71 TO STA. 123+75.92	182.21	25	506.1				21.3		42.5		0.19	1.01
STA. 121+41.42 TO STA. 122+85.57	144.15	VARIES	389.4				16.4		32.7		0.15	0.78
IL 97 (JEFFERSON ST.)												
LEFT												
STA. 110+30.77 TO STA. 115+00.00	469.23	25	1303.4				54.7		109.5		0.50	2.61
STA. 115+00.00 TO STA. 116+44.41	144.41	35	561.6				23.6		47.2		0.21	1.12
STA. 116+44.41 TO STA. 117+94.80	150.39	35.00 TO 24.00	492.9				20.7		41.4		0.19	0.99
STA. 117+94.80 TO STA. 120+09.78	214.98	24	573.3				24.1		48.2		0.22	1.15
STA. 120+09.78 TO STA. 120+59.68	49.90	24.00 TO 34.00	160.8				6.8		13.5		0.06	0.32
STA. 119+47.36 TO STA. 120+63.57	116.21	VARIES	424.6				17.8		35.7		0.16	0.85
STA. 121+57.29 TO STA. 121+81.03	23.74	40.00 TO 37.00	101.6				4.3		8.5		0.04	0.20
STA. 121+81.03 TO STA. 123+90.79	209.76	37	862.3				36.2		72.4		0.33	1.72
STA. 121+62.49 TO STA. 123+01.66	139.17	VARIES	303.9				12.8		25.5		0.12	0.61
SUB-TOTAL				0.0	159.4	7333.3	833.9	0.0	1667.8	0.0	7.5	39.7
CIDER MILL LANE												
STA. 8+20.70 TO STA. 8+70.70	50.00	36	200.0		200.0			8.4		16.8	0.08	0.40
STA. 8+70.70 TO STA. 9+52.31	81.61	36	326.4					13.7		27.4	0.12	0.65
STA. 8+20.70 TO STA. 9+54.94	134.24	VARIES	316.7					13.3		26.6	0.12	0.63
STA. 8+55.28 TO STA. 9+49.65	94.37	VARIES	317.0					13.3		26.6	0.12	0.63
STA. 10+49.75 TO STA. 12+22.69	172.94	37	711.0					29.9		59.7	0.27	1.42
STA. 10+51.59 TO STA. 11+34.10	82.51	VARIES	217.0					9.1		18.2	0.08	0.43
STA. 10+46.41 TO STA. 12+08.37	161.96	VARIES	285.6					12.0		24.0	0.11	0.57
EMPORIA AVE												
STA. 8+76.34 TO STA. 9+26.34	50.00	VARIES	176.0		176.0			7.4		14.8	0.07	0.35
STA. 9+26.34 TO STA. 9+75.73	49.39	VARIES	405.0					17.0		34.0	0.15	0.81
WINCH ROAD												
STA. 10+35.28 TO STA. 11+05.12	69.84	VARIES	147.8		147.8			6.2		12.4	0.06	0.30
STA. 11+05.12 TO STA. 11+55.12	50.00	VARIES	535.3					22.5		45.0	0.20	1.07
SIDE ROAD SUB-TOTAL				0.0	523.8	0.0		152.8	0.0	305.6	1.4	7.3
TOTAL				533.3	949.9	7,333.3	2,919.7	152.8	4,796.4	305.6	23.1	121.5

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -
c:\pw\work\p\idot\sparksgw\10290859\06723-sht-schedule.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = Oct-19-2012 03:54:14PM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
FAP 662 /67 (IL 4 /97)**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
..	1(RS),2(RS),3(RS-6)	SANGAMON	116	13
			CONTRACT NO. 72F23	
			ILLINOIS FED. AID PROJECT	