



SECTION A-A

* Existing reinforcement bars extending into the removal area shall be cleaned, straightened and incorporated into the new construction. Any reinforcement bars that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system. Cost included with Concrete Removal.

Note:
Hatched areas indicate concrete removal.

CONCRETE REMOVAL - SN: 084-0181 (SB)

DESIGNED - VP	EXAMINED - <i>Timothy A. Ballester</i>	DATE - NOVEMBER 13, 2012	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CONCRETE REMOVAL DETAILS		F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CHECKED - ATH	ACTING ENGINEER OF STRUCTURAL SERVICES			662	11RS1,21RS1,51RS-61	SANGAMON	116	98		
DRAWN - Kyle M. Steffen	PASSED - <i>Carl Perry</i>			SN 084-0181 (SB)		CONTRACT NO. 72F23				
CHECKED - VP ATH	ACTING ENGINEER OF BRIDGES AND STRUCTURES			SHEET NO. 3 OF 8 SHEETS		ILLINOIS FED. AID PROJECT				