

INDEX OF SHEETS

1. COVER
2. INDEX OF SHEETS, GENERAL NOTES, AND HIGHWAY STANDARDS
3. SUMMARY OF QUANTITIES
4. TYPICAL SECTIONS
5. SCHEDULES
6. PLAN

HIGHWAY STANDARDS

- 701001-02
- 701006-04
- 701201-04
- 701301-04
- 701306-03
- 701311-03
- 701901-03
- 780001-03

GENERAL NOTES

1. THE CONTRACTOR SHALL GIVE IDOT OPERATIONS TWO WEEKS NOTICE PRIOR TO STARTING WORK IN ORDER FOR IDOT TO COMPLETE PATCHING.
2. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
3. NO EXCAVATION IS ANTICIPATED ON THIS PROJECT. SHOULD ANY EXCAVATION BE REQUIRED, J.U.L.I.E. SHALL BE NOTIFIED A MINIMUM OF 48 HOURS IN ADVANCE (800) 892-0123.
4. ALL CONFLICTING EXISTING STRIPING SHALL BE REMOVED.
5. ALL PAVEMENT MARKINGS, AND NO PASSING ZONES SHALL BE FIELD VERIFIED BY DISTRICT 6 OPERATIONS (785-5312) 14 DAYS PRIOR TO FINAL PAVEMENT MARKINGS.
6. PAVEMENT MARKINGS SHALL NOT BE APPLIED UNTIL FINE AGGREGATE IS PROPERLY SEATED.
7. APPLICATION RATE FOR CIR-FDR EMULSIFIED ASPHALT SHALL BE 1.1 GALLON/SQ YD.
8. SEAL COAT AGGREGATE SHALL BE GRADATION CA-16 OR CA-20.
9. THE AGGREGATES FOR THE MICRO-SURFACING SHALL MEET THE FRICTION REQUIREMENTS FOR MIXTURE C IN ARTICLE 1004.03CA.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6	
EXAMINED <u>10/18</u> 20 <u>12</u>	<u>Bill Bengert</u> ENGINEER OF OPERATIONS
EXAMINED <u>Oct 9</u> 20 <u>12</u>	<u>Jimmy Jones</u> ENGINEER OF PROJECT IMPLEMENTATION
EXAMINED <u>Oct. 15</u> 20 <u>12</u>	<u>ARMLJ</u> ENGINEER OF PROGRAM DEVELOPMENT