

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE		
35400520	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 12"	SO YD	1160	1160		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	24	24		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	20	20		
42001200	PAVEMENT FABRIC	SO YD	1160	1160		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	214	214		
44004250	PAVED SHOULDER REMOVAL	SO YD	1160	1160		
50102400	CONCRETE REMOVAL	CU YD	28.8	28.8		
50157300	PROTECTIVE SHIELD	SO YD	404	404		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	28.8	28.8		
50300260	BRIDGE DECK GROOVING	SO YD	1008	1008		
50300300	PROTECTIVE COAT	SO YD	80	80		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3970	3970		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3920	3920		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE		
50800515	BAR SPLICERS	EACH	56	56		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	174	174		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	18	18		
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	18	18		
52100520	ANCHOR BOLTS, 1"	EACH	72	72		
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	1740	1740		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8		
67100100	MOBILIZATION	L SUM	1	1		
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2	2		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4		